

Stormwater Management Permit

Proposed Self Storage Facility 43 River Road Andover, Massachusetts

July 11, 2022

Prepared for:

**3P Properties, LLC
665 Church Street
Whitinsville, MA 01588**

Prepared by:

**Dana F. Perkins, Inc.
1057 East Street
Tewksbury, MA 01876**

Submitted To:

Town of Andover ~ Planning Board

Stormwater Management Permit ~ Proposed Self Storage Facility
43 River Road
Andover, Massachusetts

Project Description

The subject property is an existing 86,929 square foot lot located at 43 River Road, assessor's map 126, parcel 4. This is existing lot part of the larger property located at 43 River Road. The subject property is shown as Lot "A" on record plan #11374 recorded at the Essex North Registry of Deeds. The existing site is a vacant wooded lot. There are no existing bordering vegetated wetlands located on site.


The soils on site have been mapped by the National Resource Conservation Service (NRCS) as being comprised of Paxton and Woodbridge Fine Sandy Loam (Hydrologic Group C). Deep-hole soil observations were conducted in July of 2022 by Dana F. Perkins, Inc. The soil observations were consistent with the NRCS mapping. These observations were consistent throughout the test areas. Based on the Massachusetts Stormwater Handbook, sandy loam soils are considered to be part of Hydrologic Group B, both for recharge calculations and infiltration rates. As such, Hydrologic Group B was used to model the existing and proposed conditions.

The Applicant is proposing the construction of a 25,800 SF (footprint) self storage facility (3-story, 77,400 SF total), bituminous concrete parking and driveway areas, associated grading, utilities and stormwater management best-management practices (BMPs). To address the issues of Stormwater Management, the Applicant has proposed best management practices (BMPs), including siltation and sedimentation control, a Contech CDS hydrodynamic separator unit, and two infiltration basins to provide groundwater recharge and detention. All of the stormwater runoff from impervious area on site is proposed to be recharged. The following report shall demonstrate how the applicant intends to comply with the Standards of the Stormwater Management policies.

Stormwater Management Permit ~ Proposed Self Storage Facility
43 River Road
Andover, Massachusetts

Registered Professional Engineer's Certification

I have reviewed the Stormwater Report, including the soil evaluation, computations, Long-Term Pollution Prevention Plan, the Construction Period Erosion and Sedimentation Control Plan (if included), the Long-Term Post-Construction Operation and Maintenance Plan, the Illicit Discharge Compliance Statement (if included) and the plans showing the stormwater management system, and have determined that they have been prepared in accordance with the requirements of the Stormwater Management Standards as further elaborated by the Massachusetts Stormwater Handbook. I have also determined the information presented in the Stormwater Checklist is accurate and that the information presented in the Stormwater Report accurately reflects conditions at the site as of the date of this permit application.



Professional Engineer

Date

Stormwater Management Permit ~ Proposed Self Storage Facility
43 River Road
Andover, Massachusetts

Project Type: Is the application for new development, redevelopment, or a mix of new and redevelopment?

- New Development

LID Measures: Stormwater Standards require LID measures to be considered. Document what sensitive design and LID Techniques were considered during the planning and design of the project:

- No disturbance to any Wetland Resource Areas ~ *The applicant is proposing no alteration of any Wetland Resource Areas.*

Standard #1: No new untreated discharges:

No new stormwater conveyances (e.g., outfalls) may discharge untreated stormwater directly to or cause erosion in wetlands or waters of the Commonwealth.

- No new untreated discharges ~ *All new stormwater outfalls shall only discharge treated stormwater and clean roof runoff. The stormwater shall be recharged through the use of infiltration basins, therefore no erosion shall take place within the wetlands or water of the Commonwealth.*
- Supporting calculations specified in Volume 3 of the Massachusetts Stormwater Handbook included ~ *Supporting calculations have been included.*

Standard #2: Peak Rate Attenuation

Stormwater management systems must be designed so that post-development peak discharge rates do not exceed pre-development peak discharge rates.

- Evaluation provided to determine whether off-site flooding increases during the 100-year 24-hour storm ~ *Hydrological calculations have been provided.*
- Calculations provided to show that post-development peak discharge rates do not exceed predevelopment rates for the 2-year and 10-year 24-hour storms. If evaluations shows that off-site flooding increases during the 100-year 24-hour storm, calculations are also provided to show that post-development peak discharge rates do not exceed pre-development rates for the 100-year 24-hour storm ~ *Hydrological calculations have been provided.*

Standard #3: Recharge to groundwater

Loss of annual recharge to ground water shall be eliminated or minimized through the use of infiltration methods, including environmentally sensitive site design, low impact development techniques, best management practices, and good operation and maintenance. At a minimum, the annual recharge from the post-development site shall approximate the annual recharge from the pre-development conditions based on soil type. This Standard is met when the stormwater management system is designed to infiltrate the required recharge volume as determined in accordance with the Massachusetts Stormwater Handbook.

- Soil analysis provided ~ *The soils on site have been mapped by the National Resource Conservation Service (NRCS) as being comprised of Paxton and Woodbridge Fine Sandy Loam and have been field verified to consist of sandy loam soils. Infiltration calculations have been based on the Hydrologic Group "B" group (according to the Massachusetts Stormwater Handbook classifications for sandy loam) requirements and have been attached to this report. Deep-hole observation test pits have also been conducted.*
- Required recharge volume calculation provided ~ *Stormwater runoff from the impervious areas, to the maximum extent practicable, is being proposed to recharge through infiltration basins. The infiltration basins have been designed to infiltrate more than the required recharge volume. Calculations have been included in this report.*
- Sizing the infiltration BMP's is based on the following method: Indicate method used: *Calculations have been included in this report.*
- Runoff from all impervious areas at the site discharging to the infiltration BMP ~ *Runoff from all of the proposed impervious areas on site, to the maximum extent practicable, discharge to an infiltration BMP.*
- Calculations showing that the infiltration BMPs will drain in 72 hours are provided ~ *Calculations have been provided demonstrating that each infiltration BMP will drain in less than 72 hours.*
- Documentation is provided showing that infiltration BMPs do not adversely impact nearby wetland resource areas ~ *Runoff from the paved areas shall first be treated by deep-sump catch basin and CDS hydrodynamic separators before entering the infiltration basins. The infiltration basins will then provide further treatment to the stormwater runoff as it is being infiltrated into the ground. There are no nearby wetland resource areas located on the property.*

Standard #4: Water Quality

Stormwater Management systems must be designed to remove 80% of the average annual post-construction load of Total Suspended Solids (TSS). This standard is met when:

- a. Suitable practices for source control and pollution prevention are identified in a long-term pollution prevention plan and thereafter are implemented and maintained;
- b. Stormwater BMPs are sized to capture the required water quality volume determined in accordance with the Massachusetts Stormwater Handbook; and
- c. Pre-treatment is provided in accordance with the Massachusetts Stormwater Handbook.

■ A Long-Term Pollution Prevention Plan is attached to the Stormwater Report and is included as an attachment to the Wetlands Notice of Intent ~ *A Long-Term Pollution Prevention Plan is attached to this Stormwater Report .*

■ Treatment BMPs subject to the 44% TSS removal pretreatment requirement and the one inch rule for calculating the water quality volume are included, and discharge is: Within the Zone II or Interim Wellhead Protection Area ~ *Stormwater BMPs have been proposed to meet the 80% TSS removal requirement. The property is not located in a Zone II. Calculations have been provided.*

■ Calculations documenting that the treatment train meets the 80% TSS removal requirement and, if applicable, the 44% TSS removal pretreatment requirement, are provided ~ *Calculations documenting TSS removal are included with this report. The property is not located in a Zone II. Pretreatment is provided by deep-sump catch basins and Contech CDS hydrodynamic separator unit. Further treatment is provided by infiltration basins.*

■ The BMP is sized (and calculations provided) based on:

- The equivalent flow rate associated with the water quality volume and documentation is provided showing that the BMP treats the required water quality volume. ~ *The Contech CDS hydrodynamic separator is sized based on flow capacity Calculations have been provided that convert the runoff volume to a 1.0" Equivalent Water Quality Flow rate.*

■ The applicant proposed to use proprietary BMPs, and documentation supporting use of proprietary BMP and proposed TSS removal rate is provided. ~ *The applicant is proposing to use Contech CDS hydrodynamic separator units. Documentation has been provided.*

Standard #5: Land Uses with Higher Potential Pollutant Loads

For land uses with higher potential pollutant loads, source control and pollution prevention shall be implemented in accordance with the Massachusetts Stormwater Handbook to eliminate or reduce the discharge of stormwater runoff from such land uses to the maximum extent practicable. If through source control and/or pollution prevention, all land uses with higher potential pollutant loads cannot be completely protected from exposure to rain, snow, snow melt and stormwater runoff, the proponent shall use the specific stormwater BMPs determined by the Department to be suitable for such use as provided in the Massachusetts Stormwater Handbook. Stormwater discharges from land uses with higher potential pollutant loads shall also comply with the requirements of the Massachusetts Clean Water Act, M.G.L. c. 21, ¶ 26-53, and the regulations promulgated thereunder at 314 CMR 3.00, 314 CMR 4.00 and 314 CMR 5.00.

- The NPDES Multi-Sector General Permit does not cover the land use ~ *It is our opinion that the project does not require the filing of a NPDES Multi-Sector General Permit.*

Standard #6: Critical Areas

Stormwater discharges to a Zone II or Interim Wellhead Protection Area of a public water supply and stormwater discharges near or any other critical area require the use of the specific source control and pollution prevention measures and the specific stormwater best management practices determined by the Department to be suitable for managing discharges to such area, as provided in the Massachusetts Stormwater Handbook. A discharge is near a critical area if there is a strong likelihood of a significant impact occurring to said area, taking into account site-specific factors. Stormwater discharges to Outstanding Resource Waters or Special Resource Waters shall be set back from the receiving water and receive the highest and best practical method of treatment. A “stormwater discharge,” as defined in 314 CMR 3.04(2)(a)1. Or (b), to an Outstanding Resource Water or Special Resource Water shall comply with 314 CMR 3.00 and 314 CMR 4.00. Stormwater discharges to a Zone I or Zone A are prohibited unless essential to the operation of the public water supply.

- The discharge is near or to a critical area and the treatment train includes only BMPs that MassDEP has approved for stormwater discharges to or near that particular class of critical area ~ *The subject property is not located within a Zone II critical area. Stormwater BMPs have been designed to meet all applicable pretreatment requirements and additional local recharge requirements. Calculations have been provided.*
- Critical areas and BMPs are identified in the Stormwater Report ~ *The subject property is not located within a Zone II critical area. Stormwater BMPs have been designed to meet all applicable pretreatment requirements and additional local recharge requirements. Calculations have been provided.*

Standard #7: Redevelopments and Other Projects Subject to Standards only to the Maximum Extent Practicable.

- *The proposed project is comprised of new development. The entire site had been designed to be in compliance with all Stormwater Management Standards.*

Standard #8: Construction Period Pollution Prevention and Erosion and Sedimentation Control

A plan to control construction-related impacts, including erosion, sedimentation and other pollutant sources during construction and land disturbance activities (construction period erosion, sedimentation, and pollution prevention plan), must be developed and implemented.

- A Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan containing the information set forth above has been included in the Stormwater Report ~ *A Construction Period Pollution Prevention and Erosion and Sedimentation Control Plan has been included in the Stormwater Report.*
- The Project is covered by a NPDES Construction General ~ *Construction activities will disturb more than one acre of land and will be covered by an NPDES Construction General Permit. The SWPPP will be submitted prior to construction.*

■
Standard #9: Operation and Maintenance Plan

A long-term operation and maintenance plan must be developed and implemented to ensure that stormwater management systems function as designed.

- The Post Construction and Maintenance Plan is included in the Stormwater Report ~ *A Long-Term Pollution Prevention Plan has been prepared and included in this report and shall be implemented after construction is complete to ensure the function of the proposed BMPs on site.*

Standard #10: No illicit discharges

All illicit discharges to the stormwater management system are prohibited.

- The Long-Term Pollution Prevention Plan includes measure to prevent illicit discharges ~ *The Long-Term Pollution Prevention Plan incorporates measures to prevent illicit discharges to the stormwater system in the future.*
- No Illicit Discharge Compliance Statement is attached, but will be submitted prior to the discharge of any stormwater to post-construction BMPs ~ *An Illicit Discharge Compliance Statement is attached and must be completed prior to any construction activities taking place on site.*

Stormwater Management Permit ~ Proposed Self Storage Facility

43 River Road
Andover, Massachusetts

Illicit Discharge Compliance Statement

Illicit discharges shall not be discharged to any Stormwater Management System, prior to, throughout, or after construction. Illicit Discharges include not only wastewater, but also stormwater runoff that has become contaminated by contact with process wastes, raw materials, toxic pollutants, hazardous substances, oil or grease. An Illicit Discharge **does not** include the following activities: firefighting, water line flushing, landscape irrigation, uncontaminated groundwater, potable water sources, foundation drains, air conditioning condensation, footing drains, individual car washing, flows from riparian habitats and wetlands, dechlorinated water from swimming pools, water used for street washing and water used to clean residential buildings without detergents.

By signing below, as a Representative of the Applicant, I certify to the following:

1. No Illicit Discharges currently exist on site.
2. No Illicit Discharges are proposed on site.
3. I understand the negative impacts that Illicit Discharges could impose upon the Stormwater Management Systems, both existing and/or to be constructed on the property located at **43 River Road ~ Andover, Massachusetts**
4. I have read and understand both the **Construction Period Stormwater Pollution Prevention Plan** and the **Long-Term Stormwater Pollution Prevent Plan** and shall maintain the integrity of their inspection and maintenance procedures.
5. I shall immediately report any Illicit Discharges to the following entities:
 - a. Dana F. Perkins, Inc. ~ Engineering Department
 - b. Town of Andover ~ Board of Health
 - c. Town of Andover ~ Planning & Conservation Department

Sign Name: _____



Print Name: _____

ANDREW POTASEK - DANA F. PERKINS, INC

Date: _____

7/11/22

Stormwater Management Permit

**Proposed Self Storage Facility
43 River Road
Andover, Massachusetts**

CONSTRUCTION PERIOD POLLUTION PREVENTION PLAN

Prepared for:

**3P Properties, LLC
665 Church Street
Whitinsville, MA 01588**

Prepared by:

**Dana F. Perkins, Inc.
1057 East Street
Tewksbury, MA 01876**

Submitted To:

Town of Andover ~ Planning Board

Stormwater Management Permit ~ Proposed Self Storage Facility

**43 River Road
Andover, Massachusetts**

Construction Period Stormwater Pollution Prevention Plan

Index of Materials

- I.** General Site Map
- II.** Certifications
- III.** Construction / Implementation Checklist
- IV.** Site Description
- V.** Sequence of Major Construction Activities
- VI.** Implementation and Maintenance of Erosion and Sediment Controls
- VII.** Other Controls
- VIII.** Maintenance / Inspection Procedures
- IX.** Inventory for Pollution Prevention Plan
- X.** Spill Prevention

Appendices

Appendix A ~ Inspection Reports

Proposed Self Storage Facility
43 River Road
Andover, Massachusetts
Construction Period Pollution Prevention Plan

Stormwater Pollution Prevention Plan Certification

I hereby certify, under penalty of law, that this document and all attachments were reviewed by me, and to the best of my knowledge the information submitted is true, accurate, and complete. I am aware that there are significant penalties for knowingly submitting false information including the possibility of fines and imprisonment.

Signed: _____

(must be signed by Company Officer)

Date: _____

Proposed Self Storage Facility
43 River Road
Andover, Massachusetts
Construction Period Pollution Prevention Plan

Contractor Certification

I hereby certify, under penalty of law, that I understand the terms and conditions of the National Pollutant Discharge Elimination System (N.P.D.E.S.) that authorizes the stormwater discharges associated with the construction activities for this particular construction site as identified on this part of the certification.

Signed: _____

Representative of: (name of Construction Company)

Date: _____

Proposed Self Storage Facility
43 River Road
Andover, Massachusetts
Construction Period Pollution Prevention Plan

Construction / Implementation Checklist

1. Maintain Records of Construction Activities, including:
 - Dates when major grading activities occur.
 - Dates when construction activities temporarily cease on a portion of the site.
 - Dates when construction activities permanently cease on a portion of the site.
 - Dates when stabilization measures are initiated on the site.

2. Prepared Inspection Reports summarizing:
 - Name of inspector
 - Qualifications of inspector
 - Measures/areas inspected
 - Observed conditions
 - Changes necessary to the SWPP

3. Report Releases of Reportable Quantities of Oil or Hazardous Materials (if they occur):
 - Notify National Response Center 800-424-8802 immediately
 - Notify permitting authority in writing within 14 days
 - Modify the pollution prevention plan to include:
 - the date of release
 - circumstances leading to the release
 - steps taken to prevent reoccurrence of the release

4. Modify Pollution Prevention Plan as necessary to:
 - Comply with the minimum permit requirements when notified by EPA that the plan does not comply.
 - Address a change in design, construction operation or maintenance which has an effect on the potential for discharge of pollutants.
 - Prevent reoccurrence of reportable quantity releases of a hazardous material or oil.

Proposed Self Storage Facility
43 River Road
Andover, Massachusetts
Construction Period Pollution Prevention Plan

Site Description

Project Name: Proposed Self Storage Facility

Project Location: 43 River Road ~ Andover, MA 01810

Latitude & Longitude: 42.6923°, -71.1929°

Applicant Address: 3P Properties, LLC
665 Church Street
Whitinsville, MA 01588

**Party Responsible for Implementation
of Construction Period S.W.P.P. : SITE CONTRACTOR**

Approximate Project Area: 86,929 square-feet ±

Total Area of Disturbance: 86,929 square-feet ±

Total Proposed Impervious Area (full site): 55,102 square-feet ±

Proposed Runoff Coefficient: 0.68

Total Area of Wetland Alteration: 0

Total Area of Wetland Restoration: 0

Stormwater Management BMP's Provided:

Deep-Sump Catch Basins, Hydrodynamic separator, Infiltration basins

Utilities to be Provided:

Public water, electric, gas, and sewer services

Proposed Self Storage Facility
43 River Road
Andover, Massachusetts
Construction Period Pollution Prevention Plan

Sequence of Major Construction Activities

1. Install erosion controls as shown on the design plans.
2. Install construction fencing, as necessary.
3. Install crushed stoned apron at the proposed construction entrance.
4. Clear proposed parking areas and building site.
5. Construct proposed self storage building.
6. Preliminary site grading.
7. Install proposed drainage structures and drain lines.
8. Construct infiltration basins.
9. Install proposed utilities to building addition.
10. Finalize building construction.
11. Finalize site grading.
12. Install binder course of bituminous concrete pavement and appropriate curbing.
13. Loam and seed proposed grassed areas
14. Install proposed landscaping (ie. trees, mulched areas, etc.).
15. Install top course of bituminous concrete pavement.
16. Ensure full germination of all seeded areas. Repair any necessary areas.
17. Remove any sediment from all drainage structures.
18. Remove temporary erosion controls after entire site has been properly stabilized.

Proposed Self Storage Facility
43 River Road
Andover, Massachusetts
Construction Period Pollution Prevention Plan

Implementation and Maintenance of Erosion and Sediment Controls

Temporary Stabilization

Stockpiles of soil materials will be surrounded sediment filtermitt (or straw wattles). Areas of the site that have been stripped of topsoil and are not part of the active construction area for at least 14 days shall be temporarily stabilized with 4,000 pounds per acre of straw mulch.

Permanent Stabilization

Disturbed portions of the site where construction activities permanently cease shall be stabilized with permanent seed, hydroseed, or sod no later than 14 days after the last construction activity.

Stormwater Management

Stormwater Management BMPs shall be inspected weekly during construction. Any accumulated sediment shall be removed and disposed of according to Town of Andover regulations. During construction, sediment filtermitt (or straw wattles) shall be used to the extent practicable to direct stormwater towards pervious areas on-site rather than directly towards Stormwater Management BMPs.

Other Controls

Waste Disposal

Waste Materials: All waste materials including trash and construction debris shall be collected and stored in securely lidded metal dumpsters. Trash and/or construction debris shall not be allowed to remain exposed for any period of time. Metal dumpsters shall be emptied a minimum of once per week or more often as necessary. No construction waste materials shall be buried onsite. All personnel will be instructed regarding the proper procedure for waste disposal. It shall be the responsibility of the general contractor to ensure that these procedures are followed.

Hazardous Waste: All hazardous waste will be disposed of in the manner specified by local and/or State regulation or by the manufacturer. Site personnel will be instructed in these practices and the general contractor shall be responsible for seeing that these procedures are followed.

Sanitary Waste: All sanitary waste will be collected from the portable units as necessary by a licensed sanitary waste management contractor.

Offsite Vehicle Tracking

Dump trucks hauling material to and from the construction site shall be covered by a tarpaulin. A crushed-stone apron shall be constructed at construction site entrance to reduce offsite vehicle tracking.

Proposed Self Storage Facility
43 River Road
Andover, Massachusetts
Construction Period Pollution Prevention Plan

Maintenance / Inspection Procedures

The following maintenance and inspection procedures shall be followed so as to ensure proper erosion and sediment control throughout construction.

1. The siltation controls shall be installed prior to conducting any land-disturbing activities.
2. All erosion control measures shall be inspected once per week and following any storm event of 0.5 inches or greater.
3. Should dewatering activities be required, pumped groundwater shall be directed to a dewatering sump prior to discharge to any wetland resource area or stormwater management area.
4. All measures will be maintained in good working order and shall be repaired as necessary throughout construction. If a repair is necessary, it will be initiated within 24 hours of observation.
5. Sediment shall be removed from the erosion controls when it has accumulated to a depth of approximately 6 inches.
6. Any catch basins located immediately downstream from the construction site shall be inspected once per week and following any storm event of 0.5 inches or greater. Any significant sediment accumulation within these catch basins shall be removed within 24 hours of observation.
7. All seeded areas shall be inspected periodically to insure proper germination and adequate coverage and shall be reseeded as necessary. Any washouts shall be promptly repaired, reseeded and mulched.
8. Provide and maintain dumpsters for trash removal. Trash and construction debris shall be picked up daily.
9. The Contractor shall direct surface runoff to unpaved, pervious areas on the site to the maximum extent possible, utilizing temporary straw wattles as required preventing erosion and sedimentation of offsite areas.
10. During construction and installation of the Stormwater Management BMPs, care should be taken to minimize any sediment intrusion into these systems. Any significant sediment accumulation within these systems shall be removed within 24 hours of observation.
11. The Contractor shall make every effort to minimize the amount of impervious pavement area tributary to the drainage system and Stormwater Management BMPs until the site has been stabilized. The Contractor shall continue to direct surface runoff to unpaved areas as noted above.
12. A maintenance inspection report will be made after each inspection during construction. A copy of the report form to be completed by the inspector is attached. These reports shall be compiled and kept on site during construction. They shall be retained by the contractor for a period of 3 years.

Proposed Self Storage Facility
43 River Road
Andover, Massachusetts
Construction Period Pollution Prevention Plan

Non-Stormwater Discharges

It is expected that the following non-stormwater discharges may occur from the site during the construction period.

1. Firefighting activities
2. Water from water line flushings
3. Landscape irrigation
4. Potable water sources
5. Foundation drains
6. Air conditioning condensation
7. Footing drains
8. Individual car washing
9. Flows from riparian habitats and wetlands
10. Dechlorinated water from swimming pools
11. Building wash waters from residential buildings without detergents.
12. Pavement wash waters (where no spills or leaks of toxic or hazardous materials have occurred).
13. Uncontaminated groundwater (from dewatering excavation).

All of the above non-stormwater discharges will be directed to the pervious areas on site.

No other illicit discharges shall be permitted to discharge on site at any time. Suspected illicit discharges shall be reported to the Site Contractor immediately.

Inventory for Pollution Prevention Plan

The materials or substances listed below are expected to be present onsite during construction:

- Asphalt
- Gravel and various sized stones
- Poly-vinyl chloride piping (sewage disposal)
- Polyethylene piping (drainage)
- Copper piping (domestic water)
- Petroleum Based Products
- Fertilizer

Proposed Self Storage Facility
43 River Road
Andover, Massachusetts
Construction Period Pollution Prevention Plan

Spill Prevention

The following are the material management practices that will be used to reduce the risk of spills or other accidental exposure of materials and substances to stormwater runoff.

Good Housekeeping

The following good housekeeping practices shall be followed onsite during construction:

- An effort will be made to store only enough product as required
- All materials stored onsite will be stored in a neat, orderly manner in their appropriate containers
- Product will be kept in their original containers with the original manufacturer's label
- Substances will not be mixed with one another except as required by the manufacturer
- Whenever possible, all of a product will be used up before disposing of the container
- Materials shall be disposed of as recommended by the manufacturer.
- The site superintendent will inspect daily to ensure proper use and disposal of materials onsite

Hazardous Materials

The following practices shall be used to reduce the risks associated with hazardous materials:

- Products will be kept in original containers unless they are not resealable
- Original labels and material safety data will be retained
- If surplus product must be disposed of, manufacturer's or local and State recommended methods for proper disposal must be followed.

Product Specific Practices

The following product specific practices will be followed onsite:

Petroleum Products

All onsite vehicles will be monitored for leaks and receive regular preventative maintenance to reduce the chance of leakage. Petroleum products will be stored in tightly sealed containers which are clearly labeled. Any asphalt substances used onsite will be applied according to the manufacturer's recommendations.

Fertilizers

Fertilizers used will be applied only in the minimum amounts recommended by the manufacturer. Once applied, fertilizer will be working into the soil to limit exposure to stormwater runoff. Fertilizer shall be stored in a covered shed to prevent exposure the rain and stormwater runoff. The contents of any partially used bags of fertilizer shall be stored in sealable plastic bins to avoid spills.

Proposed Self Storage Facility
43 River Road
Andover, Massachusetts
Construction Period Pollution Prevention Plan

Spill Prevention (continued)

Paints

All containers of paint shall be tightly sealed and stored when not in use. Excess paint shall not be discharged to the stormwater drainage system but will be properly disposed of according to the manufacturer's instructions and/or State and local regulations.

Concrete Trucks

Concrete trucks will not be allowed to wash out or discharge surplus concrete or drum wash water on the site.

Spill Control Practices

In addition to the good housekeeping and material management practices previously discussed, the following practices will be followed for spill prevention and cleanup;

- Manufacturer's recommended methods of spill cleanup will be clearly posted and site personnel will be made aware of the procedures and the location of the information and cleanup supplies.
- Materials and equipment necessary for spill cleanup will be kept in the material storage area onsite. Equipment and materials will include, but are not limited to: brooms, dust pans, mops, rags, gloves, goggles, kitty litter, sand, sawdust, and plastic and metal trash containers specifically for this purpose.
- All spills will be cleaned up immediately after discovery.
- The spill area will be kept well ventilated and personnel will wear appropriate protective clothing to prevent injury from contact with a hazardous substance.
- Spills of toxic or hazardous material will be reported to the appropriate State or local government agency, regardless of size.
- The spill prevention plan will be adjusted to include measures to prevent this type of spill from reoccurring and how to clean up if another spill occurs. A description of the spill, what caused it, and the cleanup measures will also be included.
- The site superintendent responsible for the day-to-day operations will be the spill prevention and cleanup coordinator. He will designate at least three other site personnel who will receive spill prevention and cleanup training. These individuals will become responsible for a particular phase of prevention and cleanup. The names of responsible spill personnel will be posted in the material storage area and in the office trailer onsite.

Stormwater Management Permit

**Proposed Self Storage Facility
43 River Road
Andover, Massachusetts**

Appendix A

Inspection Reports

**Proposed Self Storage Facility ~ 43 River Road
Construction Period Pollution Prevention Plan**

Inspection and Maintenance Report Form

Inspector:		Date:	
Inspector Qualifications:			
Days since last rainfall:		Amount of Last Rainfall:	

Area	Date Since Last Disturbance	Method of Stabilization	Stabilized? (yes/no)	Condition

Stabilization Required:			
To be performed by:			On or before:

Inspections to be completed every 7 days and within 24 hours of
a rainfall even of 0.5 inches or more

**Proposed Self Storage Facility ~ 43 River Road
Construction Period Pollution Prevention Plan**

		Other Controls		
Inspector:			Date:	
Inspector Qualifications:				
Days since last rainfall:		Amount of Last Rainfall:		
Condition of Sediment Filtermitt: (straw wattles)				
Condition of Mulched Areas:				
Condition of Grassed Areas:				
Condition of Slopes Onsite:				
Does sediment get tracked onto adjacent roadways?				
Other observations:				
Maintenance Required:				
Inspections to be completed every 7 days and within 24 hours of a rainfall even of 0.5 inches or more				
To be performed by:			On or before:	

Stormwater Management Permit

**Proposed Self Storage Facility
43 River Road
Andover, Massachusetts**

LONG - TERM POLLUTION PREVENTION PLAN

Prepared for:

**3P Properties, LLC
665 Church Street
Whitinsville, MA 01588**

Prepared by:

**Dana F. Perkins, Inc.
1057 East Street
Tewksbury, MA 01876**

Submitted To:

Town of Andover ~ Planning Board

Proposed Self Storage Facility
43 River Road
Andover, Massachusetts
Long-Term Pollution Prevention Plan

Site Description

Project Name: Proposed Self Storage Facility

Project Location: 43 River Road ~ Andover, MA 01810

Latitude & Longitude: 42.6923°, -71.1929°

Applicant Address: 3P Properties, LLC
665 Church Street
Whitinsville, MA 01588

**Party Responsible for Implementation
of Construction Period S.W.P.P. : Property Owner**

Name of Receiving Water: All impervious areas are to be directed towards the proposed infiltration basins and recharged back into the ground.

Proposed Self Storage Facility
43 River Road
Andover, Massachusetts
Long-Term Pollution Prevention Plan

Maintenance / Inspection Procedures

The following maintenance and inspection procedures shall be followed so as to ensure proper erosion and sediment control after construction is complete and the site has become completely stabilized:

1. Inspect all embankments for erosion. Any washed out areas must be repaired, then loamed, seeded and mulched, as necessary.
2. Paved areas shall be monitored on a perpetual basis. Trash and any foreign debris shall be removed upon inspection.
3. Paved areas shall be swept at least twice per year, especially in late April or early May after the winter sanding season.
4. Any permanent dumpster(s) on site shall be fence in, covered at all times, and shall be emptied regularly.
5. Any observed litter or debris should be removed from the stormwater management areas upon observation.
6. Catch basins shall be inspected at least four times per year. Sediment shall be removed from the catch basins on a minimum annual basis, or when it has accumulated to within 2-feet of the outlet pipe elevation (sump at 50% capacity)
7. Contech Separator units shall be inspected and maintained in accordance with guidelines provided by Contech. At a minimum, the Contech units shall be inspected at least two times per year, and sediments should be removed on an annual basis, or when the depth of deposits are greater than, or equal to, half the sump depth.
8. The vian drain shall be inspected at least two times per year and cleaned out as necessary. Any debris, sediment, or other material shall be removed as needed and disposed of properly.
9. The infiltration basins shall be inspected at least two times per year. Any debris, sediment, or other material shall be removed as needed and disposed of properly.
10. Inspection reports shall be prepared and compiled for reference.

Long-Term Pollution Prevention Plan Site Inspection Report

General Information			
Project Name	Proposed Self Storage Facility		
Location	43 River Road, Andover, Massachusetts		
Date of Inspection		Start/End Time	
Inspector's Name(s) Contact Number			

	BMP/activity	Inspection Completed	Maintenance Required?	Corrective Action Needed and Notes
1	Inspect all embankments for erosion.	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
2	The street shall be swept.	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
3	Inspect catch basins	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
4	Inspect CDS Stormceptor Unit	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	
5	Inspect infiltration basins.	<input type="checkbox"/> Yes <input type="checkbox"/> No	<input type="checkbox"/> Yes <input type="checkbox"/> No	

General Notes

CERTIFICATION STATEMENT

“I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.”

Print name: _____

Signature: _____ **Date:** _____

CDS[®] Inspection and Maintenance Guide



Maintenance

The CDS system should be inspected at regular intervals and maintained when necessary to ensure optimum performance. The rate at which the system collects pollutants will depend more heavily on site activities than the size of the unit. For example, unstable soils or heavy winter sanding will cause the grit chamber to fill more quickly but regular sweeping of paved surfaces will slow accumulation.

Inspection

Inspection is the key to effective maintenance and is easily performed. Pollutant transport and deposition may vary from year to year and regular inspections will help ensure that the system is cleaned out at the appropriate time. At a minimum, inspections should be performed twice per year (e.g. spring and fall) however more frequent inspections may be necessary in climates where winter sanding operations may lead to rapid accumulations, or in equipment washdown areas. Installations should also be inspected more frequently where excessive amounts of trash are expected.

The visual inspection should ascertain that the system components are in working order and that there are no blockages or obstructions in the inlet and separation screen. The inspection should also quantify the accumulation of hydrocarbons, trash, and sediment in the system. Measuring pollutant accumulation can be done with a calibrated dipstick, tape measure or other measuring instrument. If absorbent material is used for enhanced removal of hydrocarbons, the level of discoloration of the sorbent material should also be identified during inspection. It is useful and often required as part of an operating permit to keep a record of each inspection. A simple form for doing so is provided.

Access to the CDS unit is typically achieved through two manhole access covers. One opening allows for inspection and cleanout of the separation chamber (cylinder and screen) and isolated sump. The other allows for inspection and cleanout of sediment captured and retained outside the screen. For deep units, a single manhole access point would allow both sump cleanout and access outside the screen.

The CDS system should be cleaned when the level of sediment has reached 75% of capacity in the isolated sump or when an appreciable level of hydrocarbons and trash has accumulated. If absorbent material is used, it should be replaced when significant discoloration has occurred. Performance will not be impacted until 100% of the sump capacity is exceeded however it is recommended that the system be cleaned prior to that for easier removal of sediment. The level of sediment is easily determined by measuring from finished grade down to the top of the sediment pile. To avoid underestimating the level of sediment in the chamber, the measuring device must be lowered to the top of the sediment pile carefully. Particles at the top of the pile typically offer less resistance to the end of the rod than consolidated particles toward the bottom of the pile. Once this measurement is recorded, it should be compared to the as-built drawing for the unit to determine whether the height of the sediment pile off the bottom of the sump floor exceeds 75% of the total height of isolated sump.

Cleaning

Cleaning of a CDS system should be done during dry weather conditions when no flow is entering the system. The use of a vacuum truck is generally the most effective and convenient method of removing pollutants from the system. Simply remove the manhole covers and insert the vacuum hose into the sump. The system should be completely drained down and the sump fully evacuated of sediment. The area outside the screen should also be cleaned out if pollutant build-up exists in this area.

In installations where the risk of petroleum spills is small, liquid contaminants may not accumulate as quickly as sediment. However, the system should be cleaned out immediately in the event of an oil or gasoline spill should be cleaned out immediately. Motor oil and other hydrocarbons that accumulate on a more routine basis should be removed when an appreciable layer has been captured. To remove these pollutants, it may be preferable to use absorbent pads since they are usually less expensive to dispose than the oil/water emulsion that may be created by vacuuming the oily layer. Trash and debris can be netted out to separate it from the other pollutants. The screen should be power washed to ensure it is free of trash and debris.

Manhole covers should be securely seated following cleaning activities to prevent leakage of runoff into the system from above and also to ensure that proper safety precautions have been followed. Confined space entry procedures need to be followed if physical access is required. Disposal of all material removed from the CDS system should be done in accordance with local regulations. In many jurisdictions, disposal of the sediments may be handled in the same manner as the disposal of sediments removed from catch basins or deep sump manholes.



CDS Model	Diameter		Distance from Water Surface to Top of Sediment Pile		Sediment Storage Capacity	
	ft	m	ft	m	y ³	m ³
CDS1515	3	0.9	3.0	0.9	0.5	0.4
CDS2015	4	1.2	3.0	0.9	0.9	0.7
CDS2015	5	1.3	3.0	0.9	1.3	1.0
CDS2020	5	1.3	3.5	1.1	1.3	1.0
CDS2025	5	1.3	4.0	1.2	1.3	1.0
CDS3020	6	1.8	4.0	1.2	2.1	1.6
CDS3025	6	1.8	4.0	1.2	2.1	1.6
CDS3030	6	1.8	4.6	1.4	2.1	1.6
CDS3035	6	1.8	5.0	1.5	2.1	1.6
CDS4030	8	2.4	4.6	1.4	5.6	4.3
CDS4040	8	2.4	5.7	1.7	5.6	4.3
CDS4045	8	2.4	6.2	1.9	5.6	4.3
CDS5640	10	3.0	6.3	1.9	8.7	6.7
CDS5653	10	3.0	7.7	2.3	8.7	6.7
CDS5668	10	3.0	9.3	2.8	8.7	6.7
CDS5678	10	3.0	10.3	3.1	8.7	6.7

Table 1: CDS Maintenance Indicators and Sediment Storage Capacities



Support

- Drawings and specifications are available at www.contechstormwater.com.
- Site-specific design support is available from our engineers.

©2017 Contech Engineered Solutions LLC, a QUIKRETE Company

Contech Engineered Solutions LLC provides site solutions for the civil engineering industry. Contech's portfolio includes bridges, drainage, sanitary sewer, stormwater, earth stabilization and wastewater treatment products. For information, visit www.ContechES.com or call 800.338.1122

NOTHING IN THIS CATALOG SHOULD BE CONSTRUED AS AN EXPRESSED WARRANTY OR AN IMPLIED WARRANTY OF MERCHANTABILITY OR FITNESS FOR ANY PARTICULAR PURPOSE. SEE THE CONTECH STANDARD CONDITION OF SALES (VIEWABLE AT WWW.CONTECHES.COM/COS) FOR MORE INFORMATION.

The product(s) described may be protected by one or more of the following US patents: 5,322,629; 5,624,576; 5,707,527; 5,759,415; 5,788,848; 5,985,157; 6,027,639; 6,350,374; 6,406,218; 6,641,720; 6,511,595; 6,649,048; 6,991,114; 6,998,038; 7,186,058; 7,296,692; 7,297,266; 7,517,450 related foreign patents or other patents pending.

Stormwater Management Permit

Proposed Self Storage Facility

**43 River Road
Andover, Massachusetts**

Stormwater Management Calculations

Prepared for:

**3P Properties, LLC
665 Church Street
Whitinsville, MA 01588**

Prepared by:

**Dana F. Perkins, Inc.
1057 East Street
Tewksbury, MA 01876**

Submitted To:

Town of Andover ~ Planning Board

STORMWATER CALCULATIONS

Proposed Self Storage Facility 43 River Road Andover, Massachusetts

Required Recharge Volume

Total Proposed Impervious Area = 55,102 SF ± (“B” Soils)

Infiltration Standard for “B” Soils = 0.35 inches of runoff

Required Recharge Volume = Impervious Area x Infiltration Standard

Required Volume to Recharge = 55,102 SF x (0.35 IN x 1 FT/12 IN) »» **1,607 CF**

Volume Provided in Infiltration Chambers

Storage volume provided per infiltration basin #1 = 8,254 CF ±

Storage volume provided per infiltration basin #1 = 11,454 CF ±

19,708 CF > 1,607 CF

Water Quality Treatment Volume

The stormwater runoff volume that requires treatment is equal to 1.0" of rainfall over the total new impervious areas. For the purposes of this design, existing impervious areas directed towards the hydrodynamic separator units were included. With the exception of the small area of the proposed driveway closest to River Road, all impervious paved areas are directed towards the hydrodynamic separator units.

Each infiltration basin was designed to store the water quality treatment volume for the amount of impervious area directed towards the system.

Infiltration Basin #1

Impervious area = 25,800 SF

Water quality volume = 1 IN x 1 FT/12 IN x 25,800 SF = 2,150 CF

Water quality volume provided = 8,254 CF > 2,150 CF

Infiltration Basin #2

Impervious area = 29,304 SF

Water quality volume = 1 IN x 1 FT/12 IN x 29,304 SF = 2,442 CF

Water quality volume provided = 11,454 CF > 2,442 CF

The hydrodynamic separator units are sized based on flow capacity of a 1.0" Equivalent Water Quality Flow rate.

$$WQF = (Q_u) \times (A) \times (WQV)$$

WQF = Water Quality Flow

Q_u = the unit peak discharge in CSM/IN = 795 CSM/IN

A = impervious surface drainage area in square miles

WQV = water quality volume in watershed inches = 1 IN

CDS Unit 1

A = 29,304 SF = 0.00105 MILES²

WQF = 795 CSM/IN x 0.00105 MILES² x 1 IN »» 0.83 CFS

CDS2015 Treatment Capacity = 1.4 CFS > 0.83 CFS

Infiltration BMPs ~ Draw Down Time

Infiltration Rate ("B" Soils) = 1.02 IN/HR = 0.085 FT/HR

Total storage volume provided within the infiltration basin #1 = 8,254 CF

Surface Area for Infiltration Basin #1 = 1,580 SF

Draw Down Rate (CF/HR) = 1580 SF x 0.085 FT/HR »» 134.3 CF/HR

Draw Down Time = 8,254 CF / (134.3 CF/HR) »» **61.5 hours**

72 hours > 61.5 hours

Total storage volume provided within the infiltration basin #2 = 11,454 CF

Surface Area for Infiltration Basin #2 = 2,286 SF

Draw Down Rate (CF/HR) = 2,286 SF x 0.085 FT/HR »» 194.3 CF/HR

Draw Down Time = 11,454 CF / (194.3 CF/HR) »» **59.0 hours**

72 hours > 59.0 hours

Location: Proposed Self Storage Facility ~ TSS Treatment Removal
43 River Road, Andover, MA

TSS Removal Calculation Worksheet	A	B	C	D	E
	BMP	TSS Removal Rate	Starting TSS Load*	Amount Removed (BxC)	Remaining Load (C-D)
	Deep-Sump Catch Basin	0.25	1.00*	0.25	0.75
	CDS Unit	0.65	0.75	0.49	0.26
	Infiltration Basin	0.80	0.26	0.21	0.05
	TOTAL TSS REMOVAL =			95%	

*Equals remaining load from previous BMP (E) which enters the BMP

Project: Proposed Self Storage Facility ~ 43 River Road, Andover, Massachusetts
 Prepared By: Dana F. Perkins, Inc.
 Date: July 11, 2022

Stormwater Management Permit

Proposed Self Storage Facility 43 River Road Andover, Massachusetts

Hydrological Analysis

Prepared for:

**3P Properties, LLC
43 River Road
Andover, MA 01810**

Prepared by:

**Dana F. Perkins, Inc.
1057 East Street
Tewksbury, MA 01876**

Submitted To:

Town of Andover ~ Planning Board

Stormwater Summary

Pre-development Conditions

The existing conditions stormwater runoff consists of four separate subcatchments. The majority of the existing site is directed towards the southern abutting property. Portions of the existing site are also directed towards the abutting properties to the west and the north. Finally, a small portions of the site is directed towards the Riverside Drive right of way.

Post-development Conditions

The project has been designed to capture and recharge the required recharge volume for post-development stormwater runoff on-site, with overflows directed towards the various existing design points. A HydroCAD report has been included demonstrating that the proposed stormwater system reduces peak rates of runoff below pre-development rates.

Subcatchment #1

Abutting Property to the South (3P Properties, LLC)

Storm	Existing	Proposed	Difference
2-Year (3.12")	0.07 cfs	0.05 cfs	-0.02 cfs
10-Year (4.93")	1.13 cfs	0.21 cfs	-0.92 cfs
25-Year (6.06")	2.04 cfs	0.33 cfs	-1.71 cfs
100-Year (7.80")	3.65 cfs	1.22 cfs	-2.43 cfs

Subcatchment #2

Abutting Property to the West (Greater Lawrence Vocational Technical High School)

Storm	Existing	Proposed	Difference
2-Year (3.12")	0.02 cfs	0.00 cfs	-0.02 cfs
10-Year (4.93")	0.43 cfs	0.02 cfs	-0.41 cfs
25-Year (6.06")	0.77 cfs	0.03 cfs	-0.74 cfs
100-Year (7.80")	1.38 cfs	0.05 cfs	-1.33 cfs

Subcatchment #3

Abutting Property to the North (Andover Park Development, LPT)

Storm	Existing	Proposed	Difference
2-Year (3.12")	0.01 cfs	0.01 cfs	-0.00 cfs
10-Year (4.93")	0.26 cfs	0.04 cfs	-0.22 cfs
25-Year (6.06")	0.46 cfs	0.07 cfs	-0.39 cfs
100-Year (7.80")	0.83 cfs	0.11 cfs	-0.72 cfs

Subcatchment #4- Riverside Drive (ROW)

Storm	Existing	Proposed	Difference
2-Year (3.12")	0.00 cfs	0.00 cfs	-0.00 cfs
10-Year (4.93")	0.06 cfs	0.01 cfs	-0.05 cfs
25-Year (6.06")	0.11 cfs	0.02 cfs	-0.09 cfs
100-Year (7.80")	0.20 cfs	0.03 cfs	-0.17 cfs



POINT PRECIPITATION FREQUENCY ESTIMATES

Sanja Perica, Sandra Pavlovic, Michael St. Laurent, Carl Trypaluk, Dale Unruh, Orlan Wilhite

NOAA, National Weather Service, Silver Spring, Maryland

[PF_tabular](#) | [PF_graphical](#) | [Maps & aerials](#)


PF tabular

PDS-based point precipitation frequency estimates with 90% confidence intervals (in inches)¹										
Duration	Average recurrence interval (years)									
	1	2	5	10	25	50	100	200	500	1000
5-min	0.310 (0.244-0.384)	0.369 (0.290-0.459)	0.466 (0.364-0.580)	0.547 (0.426-0.685)	0.658 (0.495-0.860)	0.742 (0.546-0.990)	0.829 (0.591-1.15)	0.926 (0.625-1.31)	1.06 (0.690-1.56)	1.18 (0.744-1.76)
10-min	0.439 (0.346-0.545)	0.523 (0.411-0.650)	0.661 (0.518-0.822)	0.775 (0.603-0.971)	0.932 (0.701-1.22)	1.05 (0.773-1.40)	1.17 (0.838-1.62)	1.31 (0.886-1.86)	1.51 (0.977-2.21)	1.67 (1.05-2.49)
15-min	0.517 (0.407-0.641)	0.616 (0.484-0.764)	0.778 (0.609-0.968)	0.912 (0.710-1.14)	1.10 (0.825-1.43)	1.24 (0.910-1.65)	1.38 (0.985-1.91)	1.54 (1.04-2.19)	1.77 (1.15-2.60)	1.96 (1.24-2.93)
30-min	0.712 (0.560-0.882)	0.848 (0.667-1.05)	1.07 (0.839-1.33)	1.26 (0.978-1.57)	1.51 (1.14-1.98)	1.70 (1.25-2.27)	1.90 (1.36-2.63)	2.13 (1.44-3.01)	2.44 (1.59-3.58)	2.70 (1.71-4.04)
60-min	0.907 (0.714-1.12)	1.08 (0.849-1.34)	1.37 (1.07-1.70)	1.60 (1.25-2.01)	1.93 (1.45-2.52)	2.17 (1.60-2.90)	2.43 (1.73-3.36)	2.71 (1.83-3.84)	3.11 (2.02-4.57)	3.44 (2.18-5.15)
2-hr	1.16 (0.921-1.43)	1.39 (1.11-1.72)	1.78 (1.40-2.20)	2.09 (1.64-2.60)	2.53 (1.92-3.30)	2.85 (2.12-3.81)	3.20 (2.32-4.45)	3.62 (2.45-5.10)	4.25 (2.76-6.19)	4.78 (3.04-7.11)
3-hr	1.34 (1.07-1.64)	1.61 (1.29-1.98)	2.07 (1.64-2.55)	2.44 (1.92-3.03)	2.96 (2.26-3.85)	3.34 (2.50-4.45)	3.75 (2.73-5.22)	4.26 (2.89-5.98)	5.05 (3.29-7.34)	5.72 (3.64-8.48)
6-hr	1.70 (1.37-2.08)	2.07 (1.66-2.52)	2.66 (2.13-3.26)	3.16 (2.51-3.89)	3.84 (2.96-4.97)	4.34 (3.28-5.76)	4.89 (3.59-6.78)	5.58 (3.80-7.79)	6.65 (4.35-9.60)	7.58 (4.83-11.2)
12-hr	2.13 (1.73-2.58)	2.61 (2.11-3.16)	3.38 (2.73-4.12)	4.03 (3.23-4.93)	4.91 (3.81-6.32)	5.56 (4.22-7.34)	6.28 (4.64-8.65)	7.16 (4.91-9.94)	8.54 (5.60-12.3)	9.73 (6.23-14.2)
24-hr	2.51 (2.05-3.02)	3.12 (2.54-3.75)	4.10 (3.34-4.96)	4.93 (3.98-5.99)	6.06 (4.73-7.76)	6.88 (5.27-9.04)	7.80 (5.80-10.7)	8.94 (6.15-12.3)	10.7 (7.08-15.3)	12.3 (7.91-17.9)
2-day	2.80 (2.31-3.35)	3.54 (2.91-4.24)	4.75 (3.89-5.71)	5.75 (4.68-6.95)	7.13 (5.62-9.11)	8.14 (6.29-10.7)	9.26 (6.97-12.7)	10.7 (7.40-14.7)	13.1 (8.63-18.5)	15.1 (9.75-21.9)
3-day	3.07 (2.54-3.66)	3.86 (3.20-4.61)	5.16 (4.25-6.17)	6.23 (5.10-7.50)	7.71 (6.11-9.81)	8.79 (6.82-11.5)	9.99 (7.55-13.7)	11.6 (8.00-15.8)	14.1 (9.33-19.9)	16.4 (10.6-23.5)
4-day	3.34 (2.77-3.97)	4.15 (3.45-4.94)	5.49 (4.54-6.55)	6.59 (5.41-7.92)	8.12 (6.45-10.3)	9.23 (7.18-12.0)	10.5 (7.93-14.3)	12.1 (8.38-16.5)	14.7 (9.75-20.7)	17.0 (11.0-24.4)
7-day	4.07 (3.41-4.81)	4.91 (4.11-5.81)	6.29 (5.24-7.47)	7.44 (6.15-8.88)	9.02 (7.20-11.3)	10.2 (7.94-13.1)	11.4 (8.69-15.5)	13.1 (9.13-17.7)	15.8 (10.5-22.1)	18.2 (11.8-25.9)
10-day	4.73 (3.98-5.57)	5.60 (4.70-6.60)	7.01 (5.86-8.30)	8.19 (6.80-9.74)	9.81 (7.85-12.3)	11.0 (8.60-14.1)	12.3 (9.33-16.5)	14.0 (9.76-18.8)	16.6 (11.1-23.2)	18.9 (12.3-26.9)
20-day	6.60 (5.60-7.73)	7.56 (6.40-8.86)	9.13 (7.70-10.7)	10.4 (8.73-12.3)	12.2 (9.81-15.1)	13.5 (10.6-17.1)	15.0 (11.3-19.6)	16.6 (11.7-22.2)	18.9 (12.7-26.2)	20.9 (13.6-29.5)
30-day	8.17 (6.97-9.53)	9.21 (7.84-10.7)	10.9 (9.23-12.8)	12.3 (10.3-14.5)	14.2 (11.5-17.4)	15.7 (12.3-19.6)	17.2 (12.9-22.2)	18.8 (13.3-25.0)	20.9 (14.1-28.8)	22.6 (14.7-31.8)
45-day	10.2 (8.72-11.8)	11.3 (9.66-13.1)	13.1 (11.2-15.3)	14.6 (12.4-17.2)	16.7 (13.5-20.3)	18.4 (14.4-22.7)	20.0 (14.9-25.4)	21.5 (15.3-28.5)	23.5 (15.9-32.2)	25.0 (16.3-35.0)
60-day	11.9 (10.2-13.8)	13.1 (11.2-15.2)	15.0 (12.8-17.5)	16.6 (14.1-19.4)	18.8 (15.3-22.8)	20.6 (16.2-25.3)	22.2 (16.7-28.2)	23.8 (17.0-31.4)	25.7 (17.4-35.2)	27.1 (17.7-37.8)


¹ Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS). Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values. Please refer to NOAA Atlas 14 document for more information.

[Back to Top](#)

PF graphical



LOCUS MAP:
NOT TO SCALE



LEGEND:

SYMBOLS AND ABBREVIATIONS SHOWN ON THIS PLAN

CONTOUR	---100---
CHAIN LINK FENCE	—o—o—o—
STOCKADE FENCE	—x—x—x—
CATCH BASIN ~ CB	⊕
DRAIN MANHOLE ~ DMH	⊙
HYDRANT	⊗
WATER VALVE	⊕
FINISH FLOOR ELEVATION	F.F.=100.00
INVERT ELEVATION	INV.=100.00
BITUMINOUS	BIT.
CONCRETE	CONC.
EXISTING	EX.
PROPOSED	PR.
SQUARE FEET	SF
NOW OR FORMERLY	N/F

NOTES:

- SUBJECT PROPERTY LOCATED ON A PORTION OF THE PROPERTY LOCATED ON ANDOVER ASSESSORS MAP #126, LOT #4. SUBJECT PROPERTY SHOWN AS LOT A ON RECORD PLAN #11374 RECORDED AT THE ESSEX NORTH REGISTRY OF DEEDS.
- SUBJECT PROPERTY LOCATED IN TOWN OF ANDOVER ZONING DISTRICT "A" ~ INDUSTRIAL A ZONING DISTRICT.
- TOPOGRAPHY AND EXISTING CONDITIONS SHOWN HEREON IS THE RESULT OF AN ON-THE-GROUND SURVEY CONDUCTED BY DANA F. PERKINS, INC., IN MAY OF 2022.

DEED REFERENCES:


ESSEX NORTH REGISTRY OF DEEDS
DEED BOOK: 1705B PAGE: 310
PLAN BOOK: PLAN #8302
PLAN BOOK: PLAN #11374

RECORD OWNERS:

3P PROPERTIES, LLC
665 CHURCH STREET
WHITINSVILLE, MA


UTILITY STATEMENT:

THE UNDERGROUND UTILITIES SHOWN HAVE BEEN LOCATED FROM FIELD SURVEY INFORMATION AND EXISTING DRAWINGS. THE SURVEYOR MAKES NO GUARANTEE THAT THE UNDERGROUND UTILITIES SHOWN COMPRISE ALL SUCH UTILITIES IN THE AREA, EITHER IN SERVICE OR ABANDONED. THE SURVEYOR FURTHER DOES NOT WARRANT THAT THE UNDERGROUND UTILITIES SHOWN ARE IN THE EXACT LOCATION INDICATED ALTHOUGH HE DOES STATE THAT THEY ARE LOCATED AS ACCURATELY AS POSSIBLE FROM INFORMATION AVAILABLE. THE SURVEYOR HAS NOT PHYSICALLY LOCATED THE UNDERGROUND UTILITIES.



DATE	BY	REVISION

N/F
GREATER LAWRENCE REGIONAL VOCATIONAL
TECHNICAL HIGH SCHOOL




N/F
AETNA REAL ESTATE ASSOC. L.P.

EXISTING DRAINAGE DIVIDE
PROPOSED SELF STORAGE FACILITY
43 RIVER ROAD
ANDOVER, MASSACHUSETTS


DANA F. PERKINS, inc.
Consulting Engineers & Land Surveyors
1057 EAST STREET ~ TEWKSBURY, MASSACHUSETTS 01876
TEL: 978-858-0680 FAX: 978-640-0237
DANA.F.PERKINS.COM

PREPARED FOR:
3P PROPERTIES, LLC
665 CHURCH STREET
WHITINSVILLE, MA

SCALE: 1" = 20' DATE: JULY 11, 2022 JOB NO. 51947 SHEET 1 OF 1



COPYRIGHT © 2022 BY DANA F. PERKINS, INC.



LOCUS MAP:
NOT TO SCALE

LEGEND:

SYMBOLS AND ABBREVIATIONS SHOWN ON THIS PLAN

- | | | |
|----------------------------------|-------|--------|
| CONTOUR | --- | 100 |
| PROPOSED CONTOUR | --- | 100 |
| PROPOSED DRAIN LINE | --- | |
| PROPOSED CATCH BASIN ~ CB | ⊙ | |
| PROPOSED DRAIN MANHOLE ~ DMH | ⊙ | |
| PROPOSED SPOT ELEVATION | • | 100x00 |
| INVERT ELEVATION | INV= | 100.00 |
| HIGH-DENSITY POLYETHYLENE (PIPE) | HDPE | |
| FINISH FLOOR ELEVATION | F.F.= | 100.00 |
| BITUMINOUS | BIT. | |
| CONCRETE | CONC. | |
| EXISTING | EX. | |
| PROPOSED | PROP. | |
| SQUARE FEET | SF | |
| TOP OF WALL ELEVATION | TW= | 100.00 |
| BOTTOM OF WALL ELEVATION | BW= | 100.00 |
| NOW OR FORMERLY | N/F | |

NOTES:

- SUBJECT PROPERTY LOCATED ON A PORTION OF THE PROPERTY LOCATED ON ANDOVER ASSESSORS MAP #126, LOT #4. SUBJECT PROPERTY SHOWN AS LOT A ON RECORD PLAN #11374 RECORDED AT THE ESSEX NORTH REGISTRY OF DEEDS.
- SUBJECT PROPERTY LOCATED IN TOWN OF ANDOVER ZONING DISTRICT "A" ~ INDUSTRIAL A ZONING DISTRICT.
- TOPOGRAPHY AND EXISTING CONDITIONS SHOWN HEREON IS THE RESULT OF AN ON-THE-GROUND SURVEY CONDUCTED BY DANA F. PERKINS, INC., IN MAY OF 2022.

DEED REFERENCES:

ESSEX NORTH REGISTRY OF DEEDS
DEED BOOK: 1705B PAGE: 310
PLAN BOOK: PLAN #8302
PLAN BOOK: PLAN #11374



RECORD OWNERS:

3P PROPERTIES, LLC
665 CHURCH STREET
WHITINSVILLE, MA

UTILITY STATEMENT:

THE UNDERGROUND UTILITIES SHOWN HAVE BEEN LOCATED FROM FIELD SURVEY INFORMATION AND EXISTING DRAWINGS. THE SURVEYOR MAKES NO GUARANTEE THAT THE UNDERGROUND UTILITIES SHOWN COMPRISE ALL SUCH UTILITIES IN THE AREA, EITHER IN SERVICE OR ABANDONED. THE SURVEYOR FURTHER DOES NOT WARRANT THAT THE UNDERGROUND UTILITIES SHOWN ARE IN THE EXACT LOCATION INDICATED ALTHOUGH HE DOES STATE THAT THEY ARE LOCATED AS ACCURATELY AS POSSIBLE FROM INFORMATION AVAILABLE. THE SURVEYOR HAS NOT PHYSICALLY LOCATED THE UNDERGROUND UTILITIES.

DATE	BY	REVISION



PROPOSED DRAINAGE DIVIDE
PROPOSED SELF STORAGE FACILITY
43 RIVER ROAD
ANDOVER, MASSACHUSETTS

SCALE: 1" = 20'


DATE: JULY 11, 2022

DANA F. PERKINS, inc.
Consulting Engineers & Land Surveyors
1057 EAST STREET ~ TEWKSBURY, MASSACHUSETTS 01876
TEL: 978-858-0680 FAX: 978-640-0237
DANA@PERKINS.COM


PREPARED FOR:
3P PROPERTIES, LLC
665 CHURCH STREET
WHITINSVILLE, MA

JOB NO. 51947


SHEET 1 OF 1



COPYRIGHT © 2022 BY DANA F. PERKINS, INC.



LOCUS MAP:
NOT TO SCALE



LEGEND:

SYMBOLS AND ABBREVIATIONS SHOWN ON THIS PLAN

CONTOUR	---100---
CHAIN LINK FENCE	—○—
STOCKADE FENCE	—□—
CATCH BASIN ~ CB	—■—
DRAIN MANHOLE ~ DMH	—●—
HYDRANT	—⊕—
WATER VALVE	—⊕—
FINISH FLOOR ELEVATION	F.F.=100.00
INVERT ELEVATION	INV.=100.00
BITUMINOUS	BIT.
CONCRETE	CONC.
EXISTING	EX.
PROPOSED	PR.
SQUARE FEET	SF
NOW OR FORMERLY	N/F

NOTES:

- SUBJECT PROPERTY LOCATED ON A PORTION OF THE PROPERTY LOCATED ON ANDOVER ASSESSORS MAP #126, LOT #4. SUBJECT PROPERTY SHOWN AS LOT A ON RECORD PLAN #11374 RECORDED AT THE ESSEX NORTH REGISTRY OF DEEDS.
- SUBJECT PROPERTY LOCATED IN TOWN OF ANDOVER ZONING DISTRICT "A" ~ INDUSTRIAL A ZONING DISTRICT.
- TOPOGRAPHY AND EXISTING CONDITIONS SHOWN HEREON IS THE RESULT OF AN ON-THE-GROUND SURVEY CONDUCTED BY DANA F. PERKINS, INC., IN MAY OF 2022.

DEED REFERENCES:


ESSEX NORTH REGISTRY OF DEEDS
DEED BOOK: 1705B PAGE: 310
PLAN BOOK: PLAN #8302
PLAN BOOK: PLAN #11374

RECORD OWNERS:

3P PROPERTIES, LLC
665 CHURCH STREET
WHITINSVILLE, MA


UTILITY STATEMENT:

THE UNDERGROUND UTILITIES SHOWN HAVE BEEN LOCATED FROM FIELD SURVEY INFORMATION AND EXISTING DRAWINGS. THE SURVEYOR MAKES NO GUARANTEE THAT THE UNDERGROUND UTILITIES SHOWN COMPRISE ALL SUCH UTILITIES IN THE AREA, EITHER IN SERVICE OR ABANDONED. THE SURVEYOR FURTHER DOES NOT WARRANT THAT THE UNDERGROUND UTILITIES SHOWN ARE IN THE EXACT LOCATION INDICATED ALTHOUGH HE DOES STATE THAT THEY ARE LOCATED AS ACCURATELY AS POSSIBLE FROM INFORMATION AVAILABLE. THE SURVEYOR HAS NOT PHYSICALLY LOCATED THE UNDERGROUND UTILITIES.



DEEP-HOLE TEST PIT INFORMATION							
TEST No.	DATE TAKEN	GROUND ELEVATION	BOTTOM ELEVATION	TOTAL DEPTH	WATER TABLE**	SOIL CLASSIFICATION	SOIL EVALUATOR
TP1	07/08/22	85.1	79.1	6.0'	79.1	SANDY LOAM	DANA F. PERKINS, INC.
TP2	07/08/22	85.9	79.9	6.0'	79.9	SANDY LOAM	DANA F. PERKINS, INC.
TP3	07/08/22	78.4	72.4	6.0'	72.4	SANDY LOAM	DANA F. PERKINS, INC.
TP4	07/08/22	79.7	74.7	5.0'	74.7	SANDY LOAM	DANA F. PERKINS, INC.

**WATER TABLE ASSUMED TO BE LOCATED AT THE BOTTOM ELEVATION OF THE TEST PIT WHERE NO OBSERVATIONS OF REDOXMORPHIC FEATURES WERE SEEN.



DATE	BY	REVISION

SOIL TEST PIT PLAN
PROPOSED SELF STORAGE FACILITY
43 RIVER ROAD
ANDOVER, MASSACHUSETTS

SCALE: 1" = 20'


DATE: JULY 11, 2022

DANA F. PERKINS, inc.
Consulting Engineers & Land Surveyors
1057 EAST STREET ~ TEWKSBURY, MASSACHUSETTS 01876
TEL: 978-858-0680 FAX: 978-640-0237
DANA.F.PERKINS.COM


PREPARED FOR:
3P PROPERTIES, LLC
665 CHURCH STREET
WHITINSVILLE, MA

JOB NO. 51947

SHEET 1 OF 1




COPYRIGHT © 2022 BY DANA F. PERKINS, INC.




Subcatchment-EX-1

Design Point




Subcatchment-EX-2

Design Point




Subcatchment-EX-3

Design Point



Subcatchment-EX-4


Design Point



Subcat



Reach



Pond



Link

Hydrology

NRCC 24-hr D 2-Year Rainfall=3.12"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 2

Time span=0.00-48.00 hrs, dt=0.01 hrs, 4801 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment EX-1: Subcatchment-EX-1	Runoff Area=52,360 sf 0.00% Impervious Runoff Depth=0.23" Tc=5.0 min CN=55 Runoff=0.07 cfs 0.023 af
Subcatchment EX-2: Subcatchment-EX-2	Runoff Area=19,809 sf 0.00% Impervious Runoff Depth=0.23" Tc=5.0 min CN=55 Runoff=0.02 cfs 0.009 af
Subcatchment EX-3: Subcatchment-EX-3	Runoff Area=11,839 sf 0.00% Impervious Runoff Depth=0.23" Tc=5.0 min CN=55 Runoff=0.01 cfs 0.005 af
Subcatchment EX-4: Subcatchment-EX-4	Runoff Area=2,933 sf 0.00% Impervious Runoff Depth=0.23" Tc=5.0 min CN=55 Runoff=0.00 cfs 0.001 af
Link DP1: Design Point	Inflow=0.07 cfs 0.023 af Primary=0.07 cfs 0.023 af
Link DP2: Design Point	Inflow=0.02 cfs 0.009 af Primary=0.02 cfs 0.009 af
Link DP3: Design Point	Inflow=0.01 cfs 0.005 af Primary=0.01 cfs 0.005 af
Link DP4: Design Point	Inflow=0.00 cfs 0.001 af Primary=0.00 cfs 0.001 af

Total Runoff Area = 1.996 ac Runoff Volume = 0.038 af Average Runoff Depth = 0.23"
100.00% Pervious = 1.996 ac 0.00% Impervious = 0.000 ac

Hydrology

NRCC 24-hr D 2-Year Rainfall=3.12"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 3

Summary for Subcatchment EX-1: Subcatchment-EX-1

Runoff = 0.07 cfs @ 12.24 hrs, Volume= 0.023 af, Depth= 0.23"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 2-Year Rainfall=3.12"

Area (sf)	CN	Description
52,360	55	Woods, Good, HSG B
52,360		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Summary for Subcatchment EX-2: Subcatchment-EX-2

Runoff = 0.02 cfs @ 12.24 hrs, Volume= 0.009 af, Depth= 0.23"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 2-Year Rainfall=3.12"

Area (sf)	CN	Description
19,809	55	Woods, Good, HSG B
19,809		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Summary for Subcatchment EX-3: Subcatchment-EX-3

Runoff = 0.01 cfs @ 12.24 hrs, Volume= 0.005 af, Depth= 0.23"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 2-Year Rainfall=3.12"

Area (sf)	CN	Description
11,839	55	Woods, Good, HSG B
11,839		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Hydrology

NRCC 24-hr D 2-Year Rainfall=3.12"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 4

Summary for Subcatchment EX-4: Subcatchment-EX-4

Runoff = 0.00 cfs @ 12.24 hrs, Volume= 0.001 af, Depth= 0.23"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 2-Year Rainfall=3.12"

Area (sf)	CN	Description
2,933	55	Woods, Good, HSG B
2,933		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Summary for Link DP1: Design Point

Inflow Area = 1.202 ac, 0.00% Impervious, Inflow Depth = 0.23" for 2-Year event
Inflow = 0.07 cfs @ 12.24 hrs, Volume= 0.023 af
Primary = 0.07 cfs @ 12.24 hrs, Volume= 0.023 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs

Summary for Link DP2: Design Point

Inflow Area = 0.455 ac, 0.00% Impervious, Inflow Depth = 0.23" for 2-Year event
Inflow = 0.02 cfs @ 12.24 hrs, Volume= 0.009 af
Primary = 0.02 cfs @ 12.24 hrs, Volume= 0.009 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs

Summary for Link DP3: Design Point

Inflow Area = 0.272 ac, 0.00% Impervious, Inflow Depth = 0.23" for 2-Year event
Inflow = 0.01 cfs @ 12.24 hrs, Volume= 0.005 af
Primary = 0.01 cfs @ 12.24 hrs, Volume= 0.005 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs

Summary for Link DP4: Design Point

Inflow Area = 0.067 ac, 0.00% Impervious, Inflow Depth = 0.23" for 2-Year event
Inflow = 0.00 cfs @ 12.24 hrs, Volume= 0.001 af
Primary = 0.00 cfs @ 12.24 hrs, Volume= 0.001 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs

Hydrology

NRCC 24-hr D 10-Year Rainfall=4.93"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 5

Time span=0.00-48.00 hrs, dt=0.01 hrs, 4801 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment EX-1: Subcatchment-EX-1	Runoff Area=52,360 sf 0.00% Impervious Runoff Depth=0.95" Tc=5.0 min CN=55 Runoff=1.13 cfs 0.095 af
Subcatchment EX-2: Subcatchment-EX-2	Runoff Area=19,809 sf 0.00% Impervious Runoff Depth=0.95" Tc=5.0 min CN=55 Runoff=0.43 cfs 0.036 af
Subcatchment EX-3: Subcatchment-EX-3	Runoff Area=11,839 sf 0.00% Impervious Runoff Depth=0.95" Tc=5.0 min CN=55 Runoff=0.26 cfs 0.021 af
Subcatchment EX-4: Subcatchment-EX-4	Runoff Area=2,933 sf 0.00% Impervious Runoff Depth=0.95" Tc=5.0 min CN=55 Runoff=0.06 cfs 0.005 af
Link DP1: Design Point	Inflow=1.13 cfs 0.095 af Primary=1.13 cfs 0.095 af
Link DP2: Design Point	Inflow=0.43 cfs 0.036 af Primary=0.43 cfs 0.036 af
Link DP3: Design Point	Inflow=0.26 cfs 0.021 af Primary=0.26 cfs 0.021 af
Link DP4: Design Point	Inflow=0.06 cfs 0.005 af Primary=0.06 cfs 0.005 af

Total Runoff Area = 1.996 ac Runoff Volume = 0.157 af Average Runoff Depth = 0.95"
100.00% Pervious = 1.996 ac 0.00% Impervious = 0.000 ac

Hydrology

NRCC 24-hr D 10-Year Rainfall=4.93"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 6

Summary for Subcatchment EX-1: Subcatchment-EX-1

Runoff = 1.13 cfs @ 12.13 hrs, Volume= 0.095 af, Depth= 0.95"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 10-Year Rainfall=4.93"

Area (sf)	CN	Description
52,360	55	Woods, Good, HSG B
52,360		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Summary for Subcatchment EX-2: Subcatchment-EX-2

Runoff = 0.43 cfs @ 12.13 hrs, Volume= 0.036 af, Depth= 0.95"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 10-Year Rainfall=4.93"

Area (sf)	CN	Description
19,809	55	Woods, Good, HSG B
19,809		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Summary for Subcatchment EX-3: Subcatchment-EX-3

Runoff = 0.26 cfs @ 12.13 hrs, Volume= 0.021 af, Depth= 0.95"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 10-Year Rainfall=4.93"

Area (sf)	CN	Description
11,839	55	Woods, Good, HSG B
11,839		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Hydrology

NRCC 24-hr D 10-Year Rainfall=4.93"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 7

Summary for Subcatchment EX-4: Subcatchment-EX-4

Runoff = 0.06 cfs @ 12.13 hrs, Volume= 0.005 af, Depth= 0.95"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 10-Year Rainfall=4.93"

Area (sf)	CN	Description
2,933	55	Woods, Good, HSG B
2,933		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Summary for Link DP1: Design Point

Inflow Area = 1.202 ac, 0.00% Impervious, Inflow Depth = 0.95" for 10-Year event
Inflow = 1.13 cfs @ 12.13 hrs, Volume= 0.095 af
Primary = 1.13 cfs @ 12.13 hrs, Volume= 0.095 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs

Summary for Link DP2: Design Point

Inflow Area = 0.455 ac, 0.00% Impervious, Inflow Depth = 0.95" for 10-Year event
Inflow = 0.43 cfs @ 12.13 hrs, Volume= 0.036 af
Primary = 0.43 cfs @ 12.13 hrs, Volume= 0.036 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs

Summary for Link DP3: Design Point

Inflow Area = 0.272 ac, 0.00% Impervious, Inflow Depth = 0.95" for 10-Year event
Inflow = 0.26 cfs @ 12.13 hrs, Volume= 0.021 af
Primary = 0.26 cfs @ 12.13 hrs, Volume= 0.021 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs

Summary for Link DP4: Design Point

Inflow Area = 0.067 ac, 0.00% Impervious, Inflow Depth = 0.95" for 10-Year event
Inflow = 0.06 cfs @ 12.13 hrs, Volume= 0.005 af
Primary = 0.06 cfs @ 12.13 hrs, Volume= 0.005 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs

Hydrology

NRCC 24-hr D 25-Year Rainfall=6.06"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 8

Time span=0.00-48.00 hrs, dt=0.01 hrs, 4801 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment EX-1: Subcatchment-EX-1	Runoff Area=52,360 sf 0.00% Impervious Runoff Depth=1.55" Tc=5.0 min CN=55 Runoff=2.04 cfs 0.156 af
Subcatchment EX-2: Subcatchment-EX-2	Runoff Area=19,809 sf 0.00% Impervious Runoff Depth=1.55" Tc=5.0 min CN=55 Runoff=0.77 cfs 0.059 af
Subcatchment EX-3: Subcatchment-EX-3	Runoff Area=11,839 sf 0.00% Impervious Runoff Depth=1.55" Tc=5.0 min CN=55 Runoff=0.46 cfs 0.035 af
Subcatchment EX-4: Subcatchment-EX-4	Runoff Area=2,933 sf 0.00% Impervious Runoff Depth=1.55" Tc=5.0 min CN=55 Runoff=0.11 cfs 0.009 af
Link DP1: Design Point	Inflow=2.04 cfs 0.156 af Primary=2.04 cfs 0.156 af
Link DP2: Design Point	Inflow=0.77 cfs 0.059 af Primary=0.77 cfs 0.059 af
Link DP3: Design Point	Inflow=0.46 cfs 0.035 af Primary=0.46 cfs 0.035 af
Link DP4: Design Point	Inflow=0.11 cfs 0.009 af Primary=0.11 cfs 0.009 af

Total Runoff Area = 1.996 ac Runoff Volume = 0.258 af Average Runoff Depth = 1.55"
100.00% Pervious = 1.996 ac 0.00% Impervious = 0.000 ac

Hydrology

NRCC 24-hr D 25-Year Rainfall=6.06"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 9

Summary for Subcatchment EX-1: Subcatchment-EX-1

Runoff = 2.04 cfs @ 12.13 hrs, Volume= 0.156 af, Depth= 1.55"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 25-Year Rainfall=6.06"

Area (sf)	CN	Description
52,360	55	Woods, Good, HSG B
52,360		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Summary for Subcatchment EX-2: Subcatchment-EX-2

Runoff = 0.77 cfs @ 12.13 hrs, Volume= 0.059 af, Depth= 1.55"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 25-Year Rainfall=6.06"

Area (sf)	CN	Description
19,809	55	Woods, Good, HSG B
19,809		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Summary for Subcatchment EX-3: Subcatchment-EX-3

Runoff = 0.46 cfs @ 12.13 hrs, Volume= 0.035 af, Depth= 1.55"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 25-Year Rainfall=6.06"

Area (sf)	CN	Description
11,839	55	Woods, Good, HSG B
11,839		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Hydrology

NRCC 24-hr D 25-Year Rainfall=6.06"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 10

Summary for Subcatchment EX-4: Subcatchment-EX-4

Runoff = 0.11 cfs @ 12.13 hrs, Volume= 0.009 af, Depth= 1.55"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 25-Year Rainfall=6.06"

Area (sf)	CN	Description
2,933	55	Woods, Good, HSG B
2,933		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Summary for Link DP1: Design Point

Inflow Area = 1.202 ac, 0.00% Impervious, Inflow Depth = 1.55" for 25-Year event
Inflow = 2.04 cfs @ 12.13 hrs, Volume= 0.156 af
Primary = 2.04 cfs @ 12.13 hrs, Volume= 0.156 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs

Summary for Link DP2: Design Point

Inflow Area = 0.455 ac, 0.00% Impervious, Inflow Depth = 1.55" for 25-Year event
Inflow = 0.77 cfs @ 12.13 hrs, Volume= 0.059 af
Primary = 0.77 cfs @ 12.13 hrs, Volume= 0.059 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs

Summary for Link DP3: Design Point

Inflow Area = 0.272 ac, 0.00% Impervious, Inflow Depth = 1.55" for 25-Year event
Inflow = 0.46 cfs @ 12.13 hrs, Volume= 0.035 af
Primary = 0.46 cfs @ 12.13 hrs, Volume= 0.035 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs

Summary for Link DP4: Design Point

Inflow Area = 0.067 ac, 0.00% Impervious, Inflow Depth = 1.55" for 25-Year event
Inflow = 0.11 cfs @ 12.13 hrs, Volume= 0.009 af
Primary = 0.11 cfs @ 12.13 hrs, Volume= 0.009 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs

Hydrology

NRCC 24-hr D 100-Year Rainfall=7.80"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 11

Time span=0.00-48.00 hrs, dt=0.01 hrs, 4801 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment EX-1: Subcatchment-EX-1	Runoff Area=52,360 sf 0.00% Impervious Runoff Depth=2.65" Tc=5.0 min CN=55 Runoff=3.65 cfs 0.265 af
Subcatchment EX-2: Subcatchment-EX-2	Runoff Area=19,809 sf 0.00% Impervious Runoff Depth=2.65" Tc=5.0 min CN=55 Runoff=1.38 cfs 0.100 af
Subcatchment EX-3: Subcatchment-EX-3	Runoff Area=11,839 sf 0.00% Impervious Runoff Depth=2.65" Tc=5.0 min CN=55 Runoff=0.83 cfs 0.060 af
Subcatchment EX-4: Subcatchment-EX-4	Runoff Area=2,933 sf 0.00% Impervious Runoff Depth=2.65" Tc=5.0 min CN=55 Runoff=0.20 cfs 0.015 af
Link DP1: Design Point	Inflow=3.65 cfs 0.265 af Primary=3.65 cfs 0.265 af
Link DP2: Design Point	Inflow=1.38 cfs 0.100 af Primary=1.38 cfs 0.100 af
Link DP3: Design Point	Inflow=0.83 cfs 0.060 af Primary=0.83 cfs 0.060 af
Link DP4: Design Point	Inflow=0.20 cfs 0.015 af Primary=0.20 cfs 0.015 af

Total Runoff Area = 1.996 ac Runoff Volume = 0.440 af Average Runoff Depth = 2.65"
100.00% Pervious = 1.996 ac 0.00% Impervious = 0.000 ac

Hydrology

NRCC 24-hr D 100-Year Rainfall=7.80"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 12

Summary for Subcatchment EX-1: Subcatchment-EX-1

Runoff = 3.65 cfs @ 12.13 hrs, Volume= 0.265 af, Depth= 2.65"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 100-Year Rainfall=7.80"

Area (sf)	CN	Description
52,360	55	Woods, Good, HSG B
52,360		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Summary for Subcatchment EX-2: Subcatchment-EX-2

Runoff = 1.38 cfs @ 12.13 hrs, Volume= 0.100 af, Depth= 2.65"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 100-Year Rainfall=7.80"

Area (sf)	CN	Description
19,809	55	Woods, Good, HSG B
19,809		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Summary for Subcatchment EX-3: Subcatchment-EX-3

Runoff = 0.83 cfs @ 12.13 hrs, Volume= 0.060 af, Depth= 2.65"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 100-Year Rainfall=7.80"

Area (sf)	CN	Description
11,839	55	Woods, Good, HSG B
11,839		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Hydrology

NRCC 24-hr D 100-Year Rainfall=7.80"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 13

Summary for Subcatchment EX-4: Subcatchment-EX-4

Runoff = 0.20 cfs @ 12.13 hrs, Volume= 0.015 af, Depth= 2.65"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 100-Year Rainfall=7.80"

Area (sf)	CN	Description
2,933	55	Woods, Good, HSG B
2,933		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Summary for Link DP1: Design Point

Inflow Area = 1.202 ac, 0.00% Impervious, Inflow Depth = 2.65" for 100-Year event
Inflow = 3.65 cfs @ 12.13 hrs, Volume= 0.265 af
Primary = 3.65 cfs @ 12.13 hrs, Volume= 0.265 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs

Summary for Link DP2: Design Point

Inflow Area = 0.455 ac, 0.00% Impervious, Inflow Depth = 2.65" for 100-Year event
Inflow = 1.38 cfs @ 12.13 hrs, Volume= 0.100 af
Primary = 1.38 cfs @ 12.13 hrs, Volume= 0.100 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs

Summary for Link DP3: Design Point


Inflow Area = 0.272 ac, 0.00% Impervious, Inflow Depth = 2.65" for 100-Year event
Inflow = 0.83 cfs @ 12.13 hrs, Volume= 0.060 af
Primary = 0.83 cfs @ 12.13 hrs, Volume= 0.060 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs

Summary for Link DP4: Design Point

Inflow Area = 0.067 ac, 0.00% Impervious, Inflow Depth = 2.65" for 100-Year event
Inflow = 0.20 cfs @ 12.13 hrs, Volume= 0.015 af
Primary = 0.20 cfs @ 12.13 hrs, Volume= 0.015 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs



PR-1A

Subcatchment-PR-1A

1P

Infiltration Pond #1

PR-1B

Subcatchment-PR-1B

2P

Infiltration Pond #2

PR-1C

Subcatchment-PR-1C

DP-1P

Design Point

PR-2

Subcatchment-PR-2

DP-2P

Design Point

PR-3

Subcatchment-PR-3

DP-3P


Design Point

PR-4

Subcatchment-PR-4

DP-4P

Design Point



Routing Diagram for Hydrology

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Hydrology

NRCC 24-hr D 2-Year Rainfall=3.12"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 2

Time span=0.00-48.00 hrs, dt=0.01 hrs, 4801 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment PR-1A:	Runoff Area=33,035 sf 78.10% Impervious Runoff Depth=2.09" Tc=5.0 min CN=90 Runoff=1.80 cfs 0.132 af
Subcatchment PR-1B:	Runoff Area=45,630 sf 64.22% Impervious Runoff Depth=1.69" Tc=5.0 min CN=85 Runoff=2.06 cfs 0.147 af
Subcatchment PR-1C: Subcatchment-PR-1C	Runoff Area=6,115 sf 0.00% Impervious Runoff Depth=0.41" Tc=5.0 min CN=61 Runoff=0.05 cfs 0.005 af
Subcatchment PR-2: Subcatchment-PR-2	Runoff Area=548 sf 0.00% Impervious Runoff Depth=0.41" Tc=5.0 min CN=61 Runoff=0.00 cfs 0.000 af
Subcatchment PR-3: Subcatchment-PR-3	Runoff Area=1,281 sf 0.00% Impervious Runoff Depth=0.41" Tc=5.0 min CN=61 Runoff=0.01 cfs 0.001 af
Subcatchment PR-4: Subcatchment-PR-4	Runoff Area=319 sf 0.00% Impervious Runoff Depth=0.41" Tc=5.0 min CN=61 Runoff=0.00 cfs 0.000 af
Pond 1P: Infiltration Pond #1	Peak Elev=84.21' Storage=2,901 cf Inflow=1.80 cfs 0.132 af Discarded=0.08 cfs 0.132 af Primary=0.00 cfs 0.000 af Outflow=0.08 cfs 0.132 af
Pond 2P: Infiltration Pond #2	Peak Elev=78.17' Storage=3,283 cf Inflow=2.06 cfs 0.147 af Discarded=0.08 cfs 0.147 af Primary=0.00 cfs 0.000 af Outflow=0.08 cfs 0.147 af
Link DP-1P: Design Point	Inflow=0.05 cfs 0.005 af Primary=0.05 cfs 0.005 af
Link DP-2P: Design Point	Inflow=0.00 cfs 0.000 af Primary=0.00 cfs 0.000 af
Link DP-3P: Design Point	Inflow=0.01 cfs 0.001 af Primary=0.01 cfs 0.001 af
Link DP-4P: Design Point	Inflow=0.00 cfs 0.000 af Primary=0.00 cfs 0.000 af

Total Runoff Area = 1.996 ac Runoff Volume = 0.286 af Average Runoff Depth = 1.72"
36.61% Pervious = 0.731 ac 63.39% Impervious = 1.265 ac

Hydrology

NRCC 24-hr D 2-Year Rainfall=3.12"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 3

Summary for Subcatchment PR-1A: Subcatchment-PR-1A

Runoff = 1.80 cfs @ 12.12 hrs, Volume= 0.132 af, Depth= 2.09"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 2-Year Rainfall=3.12"

Area (sf)	CN	Description
25,800	98	Roofs, HSG A
7,235	61	>75% Grass cover, Good, HSG B
33,035	90	Weighted Average
7,235		21.90% Pervious Area
25,800		78.10% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Summary for Subcatchment PR-1B: Subcatchment-PR-1B

Runoff = 2.06 cfs @ 12.12 hrs, Volume= 0.147 af, Depth= 1.69"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 2-Year Rainfall=3.12"

Area (sf)	CN	Description
29,304	98	Paved parking, HSG A
16,326	61	>75% Grass cover, Good, HSG B
45,630	85	Weighted Average
16,326		35.78% Pervious Area
29,304		64.22% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Summary for Subcatchment PR-1C: Subcatchment-PR-1C

Runoff = 0.05 cfs @ 12.14 hrs, Volume= 0.005 af, Depth= 0.41"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 2-Year Rainfall=3.12"

Area (sf)	CN	Description
6,115	61	>75% Grass cover, Good, HSG B
6,115		100.00% Pervious Area

Hydrology

NRCC 24-hr D 2-Year Rainfall=3.12"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 4

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Summary for Subcatchment PR-2: Subcatchment-PR-2

Runoff = 0.00 cfs @ 12.14 hrs, Volume= 0.000 af, Depth= 0.41"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 2-Year Rainfall=3.12"

Area (sf)	CN	Description
548	61	>75% Grass cover, Good, HSG B
548		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Summary for Subcatchment PR-3: Subcatchment-PR-3

Runoff = 0.01 cfs @ 12.14 hrs, Volume= 0.001 af, Depth= 0.41"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 2-Year Rainfall=3.12"

Area (sf)	CN	Description
1,281	61	>75% Grass cover, Good, HSG B
1,281		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Summary for Subcatchment PR-4: Subcatchment-PR-4

Runoff = 0.00 cfs @ 12.14 hrs, Volume= 0.000 af, Depth= 0.41"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 2-Year Rainfall=3.12"

Area (sf)	CN	Description
319	61	>75% Grass cover, Good, HSG B
319		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Hydrology

NRCC 24-hr D 2-Year Rainfall=3.12"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 5

Summary for Pond 1P: Infiltration Pond #1

Inflow Area = 0.758 ac, 78.10% Impervious, Inflow Depth = 2.09" for 2-Year event
Inflow = 1.80 cfs @ 12.12 hrs, Volume= 0.132 af
Outflow = 0.08 cfs @ 14.93 hrs, Volume= 0.132 af, Atten= 96%, Lag= 168.6 min
Discarded = 0.08 cfs @ 14.93 hrs, Volume= 0.132 af
Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Stor-Ind method, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
Peak Elev= 84.21' @ 14.93 hrs Surf.Area= 3,231 sf Storage= 2,901 cf

Plug-Flow detention time= 427.5 min calculated for 0.132 af (100% of inflow)
Center-of-Mass det. time= 427.6 min (1,252.2 - 824.6)

Volume	Invert	Avail.Storage	Storage Description
#1	83.00'	10,975 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
83.00	1,580	0	0
84.00	2,940	2,260	2,260
85.00	4,340	3,640	5,900
86.00	5,810	5,075	10,975

Device	Routing	Invert	Outlet Devices
#1	Discarded	83.00'	1.020 in/hr Exfiltration over Surface area
#2	Primary	85.50'	30.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s) 0.5' Crest Height

Discarded OutFlow Max=0.08 cfs @ 14.93 hrs HW=84.21' (Free Discharge)
↑1=Exfiltration (Exfiltration Controls 0.08 cfs)

Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=83.00' (Free Discharge)
↑2=Sharp-Crested Rectangular Weir (Controls 0.00 cfs)

Summary for Pond 2P: Infiltration Pond #2

Inflow Area = 1.048 ac, 64.22% Impervious, Inflow Depth = 1.69" for 2-Year event
Inflow = 2.06 cfs @ 12.12 hrs, Volume= 0.147 af
Outflow = 0.08 cfs @ 15.97 hrs, Volume= 0.147 af, Atten= 96%, Lag= 231.0 min
Discarded = 0.08 cfs @ 15.97 hrs, Volume= 0.147 af
Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Stor-Ind method, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
Peak Elev= 78.17' @ 15.97 hrs Surf.Area= 3,323 sf Storage= 3,283 cf

Plug-Flow detention time= 469.8 min calculated for 0.147 af (100% of inflow)
Center-of-Mass det. time= 469.9 min (1,319.6 - 849.7)

Hydrology

NRCC 24-hr D 2-Year Rainfall=3.12"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 6

Volume	Invert	Avail.Storage	Storage Description
#1	77.00'	16,546 cf	Custom Stage Data (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
77.00	2,286	0	0
78.00	3,162	2,724	2,724
79.00	4,094	3,628	6,352
80.00	5,083	4,589	10,941
81.00	6,128	5,606	16,546

Device	Routing	Invert	Outlet Devices
#1	Discarded	77.00'	1.020 in/hr Exfiltration over Surface area
#2	Primary	80.10'	10.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s) 0.5' Crest Height

Discarded OutFlow Max=0.08 cfs @ 15.97 hrs HW=78.17' (Free Discharge)

↑**1=Exfiltration** (Exfiltration Controls 0.08 cfs)

Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=77.00' (Free Discharge)

↑**2=Sharp-Crested Rectangular Weir** (Controls 0.00 cfs)

Summary for Link DP-1P: Design Point

Inflow Area = 1.946 ac, 65.00% Impervious, Inflow Depth = 0.03" for 2-Year event
Inflow = 0.05 cfs @ 12.14 hrs, Volume= 0.005 af
Primary = 0.05 cfs @ 12.14 hrs, Volume= 0.005 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs

Summary for Link DP-2P: Design Point

Inflow Area = 0.013 ac, 0.00% Impervious, Inflow Depth = 0.41" for 2-Year event
Inflow = 0.00 cfs @ 12.14 hrs, Volume= 0.000 af
Primary = 0.00 cfs @ 12.14 hrs, Volume= 0.000 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs

Summary for Link DP-3P: Design Point

Inflow Area = 0.029 ac, 0.00% Impervious, Inflow Depth = 0.41" for 2-Year event
Inflow = 0.01 cfs @ 12.14 hrs, Volume= 0.001 af
Primary = 0.01 cfs @ 12.14 hrs, Volume= 0.001 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs

Hydrology

NRCC 24-hr D 2-Year Rainfall=3.12"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 7

Summary for Link DP-4P: Design Point

Inflow Area = 0.007 ac, 0.00% Impervious, Inflow Depth = 0.41" for 2-Year event
Inflow = 0.00 cfs @ 12.14 hrs, Volume= 0.000 af
Primary = 0.00 cfs @ 12.14 hrs, Volume= 0.000 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs

Hydrology

NRCC 24-hr D 10-Year Rainfall=4.93"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 8

Time span=0.00-48.00 hrs, dt=0.01 hrs, 4801 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment PR-1A: Runoff Area=33,035 sf 78.10% Impervious Runoff Depth=3.81"
Tc=5.0 min CN=90 Runoff=3.17 cfs 0.241 af

Subcatchment PR-1B: Runoff Area=45,630 sf 64.22% Impervious Runoff Depth=3.30"
Tc=5.0 min CN=85 Runoff=3.93 cfs 0.288 af

Subcatchment PR-1C: Subcatchment-PR-1C Runoff Area=6,115 sf 0.00% Impervious Runoff Depth=1.33"
Tc=5.0 min CN=61 Runoff=0.21 cfs 0.016 af

Subcatchment PR-2: Subcatchment-PR-2 Runoff Area=548 sf 0.00% Impervious Runoff Depth=1.33"
Tc=5.0 min CN=61 Runoff=0.02 cfs 0.001 af

Subcatchment PR-3: Subcatchment-PR-3 Runoff Area=1,281 sf 0.00% Impervious Runoff Depth=1.33"
Tc=5.0 min CN=61 Runoff=0.04 cfs 0.003 af

Subcatchment PR-4: Subcatchment-PR-4 Runoff Area=319 sf 0.00% Impervious Runoff Depth=1.33"
Tc=5.0 min CN=61 Runoff=0.01 cfs 0.001 af

Pond 1P: Infiltration Pond #1 Peak Elev=85.02' Storage=6,003 cf Inflow=3.17 cfs 0.241 af
Discarded=0.10 cfs 0.241 af Primary=0.00 cfs 0.000 af Outflow=0.10 cfs 0.241 af

Pond 2P: Infiltration Pond #2 Peak Elev=79.29' Storage=7,597 cf Inflow=3.93 cfs 0.288 af
Discarded=0.10 cfs 0.280 af Primary=0.00 cfs 0.000 af Outflow=0.10 cfs 0.280 af

Link DP-1P: Design Point Inflow=0.21 cfs 0.016 af
Primary=0.21 cfs 0.016 af

Link DP-2P: Design Point Inflow=0.02 cfs 0.001 af
Primary=0.02 cfs 0.001 af

Link DP-3P: Design Point Inflow=0.04 cfs 0.003 af
Primary=0.04 cfs 0.003 af

Link DP-4P: Design Point Inflow=0.01 cfs 0.001 af
Primary=0.01 cfs 0.001 af

Total Runoff Area = 1.996 ac Runoff Volume = 0.550 af Average Runoff Depth = 3.31"
36.61% Pervious = 0.731 ac 63.39% Impervious = 1.265 ac

Hydrology

NRCC 24-hr D 10-Year Rainfall=4.93"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 9

Summary for Subcatchment PR-1A: Subcatchment-PR-1A

Runoff = 3.17 cfs @ 12.12 hrs, Volume= 0.241 af, Depth= 3.81"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 10-Year Rainfall=4.93"

Area (sf)	CN	Description
25,800	98	Roofs, HSG A
7,235	61	>75% Grass cover, Good, HSG B
33,035	90	Weighted Average
7,235		21.90% Pervious Area
25,800		78.10% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Summary for Subcatchment PR-1B: Subcatchment-PR-1B

Runoff = 3.93 cfs @ 12.12 hrs, Volume= 0.288 af, Depth= 3.30"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 10-Year Rainfall=4.93"

Area (sf)	CN	Description
29,304	98	Paved parking, HSG A
16,326	61	>75% Grass cover, Good, HSG B
45,630	85	Weighted Average
16,326		35.78% Pervious Area
29,304		64.22% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Summary for Subcatchment PR-1C: Subcatchment-PR-1C

Runoff = 0.21 cfs @ 12.13 hrs, Volume= 0.016 af, Depth= 1.33"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 10-Year Rainfall=4.93"

Area (sf)	CN	Description
6,115	61	>75% Grass cover, Good, HSG B
6,115		100.00% Pervious Area

Hydrology

NRCC 24-hr D 10-Year Rainfall=4.93"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 10

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Summary for Subcatchment PR-2: Subcatchment-PR-2

Runoff = 0.02 cfs @ 12.13 hrs, Volume= 0.001 af, Depth= 1.33"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 10-Year Rainfall=4.93"

Area (sf)	CN	Description
548	61	>75% Grass cover, Good, HSG B
548		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Summary for Subcatchment PR-3: Subcatchment-PR-3

Runoff = 0.04 cfs @ 12.13 hrs, Volume= 0.003 af, Depth= 1.33"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 10-Year Rainfall=4.93"

Area (sf)	CN	Description
1,281	61	>75% Grass cover, Good, HSG B
1,281		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Summary for Subcatchment PR-4: Subcatchment-PR-4

Runoff = 0.01 cfs @ 12.13 hrs, Volume= 0.001 af, Depth= 1.33"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 10-Year Rainfall=4.93"

Area (sf)	CN	Description
319	61	>75% Grass cover, Good, HSG B
319		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Hydrology

NRCC 24-hr D 10-Year Rainfall=4.93"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 11

Summary for Pond 1P: Infiltration Pond #1

Inflow Area = 0.758 ac, 78.10% Impervious, Inflow Depth = 3.81" for 10-Year event
Inflow = 3.17 cfs @ 12.12 hrs, Volume= 0.241 af
Outflow = 0.10 cfs @ 16.14 hrs, Volume= 0.241 af, Atten= 97%, Lag= 241.0 min
Discarded = 0.10 cfs @ 16.14 hrs, Volume= 0.241 af
Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Stor-Ind method, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
Peak Elev= 85.02' @ 16.14 hrs Surf.Area= 4,375 sf Storage= 6,003 cf

Plug-Flow detention time= 664.8 min calculated for 0.241 af (100% of inflow)
Center-of-Mass det. time= 664.8 min (1,467.8 - 803.0)

Volume	Invert	Avail.Storage	Storage Description
#1	83.00'	10,975 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
83.00	1,580	0	0
84.00	2,940	2,260	2,260
85.00	4,340	3,640	5,900
86.00	5,810	5,075	10,975

Device	Routing	Invert	Outlet Devices
#1	Discarded	83.00'	1.020 in/hr Exfiltration over Surface area
#2	Primary	85.50'	30.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s) 0.5' Crest Height

Discarded OutFlow Max=0.10 cfs @ 16.14 hrs HW=85.02' (Free Discharge)
↑1=Exfiltration (Exfiltration Controls 0.10 cfs)

Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=83.00' (Free Discharge)
↑2=Sharp-Crested Rectangular Weir (Controls 0.00 cfs)

Summary for Pond 2P: Infiltration Pond #2

Inflow Area = 1.048 ac, 64.22% Impervious, Inflow Depth = 3.30" for 10-Year event
Inflow = 3.93 cfs @ 12.12 hrs, Volume= 0.288 af
Outflow = 0.10 cfs @ 17.74 hrs, Volume= 0.280 af, Atten= 97%, Lag= 336.9 min
Discarded = 0.10 cfs @ 17.74 hrs, Volume= 0.280 af
Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Stor-Ind method, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
Peak Elev= 79.29' @ 17.74 hrs Surf.Area= 4,385 sf Storage= 7,597 cf

Plug-Flow detention time= 797.1 min calculated for 0.280 af (97% of inflow)
Center-of-Mass det. time= 779.9 min (1,604.8 - 824.9)

Hydrology

NRCC 24-hr D 10-Year Rainfall=4.93"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 12

Volume	Invert	Avail.Storage	Storage Description
#1	77.00'	16,546 cf	Custom Stage Data (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
77.00	2,286	0	0
78.00	3,162	2,724	2,724
79.00	4,094	3,628	6,352
80.00	5,083	4,589	10,941
81.00	6,128	5,606	16,546

Device	Routing	Invert	Outlet Devices
#1	Discarded	77.00'	1.020 in/hr Exfiltration over Surface area
#2	Primary	80.10'	10.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s) 0.5' Crest Height

Discarded OutFlow Max=0.10 cfs @ 17.74 hrs HW=79.29' (Free Discharge)

↑**1=Exfiltration** (Exfiltration Controls 0.10 cfs)

Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=77.00' (Free Discharge)

↑**2=Sharp-Crested Rectangular Weir** (Controls 0.00 cfs)

Summary for Link DP-1P: Design Point

Inflow Area = 1.946 ac, 65.00% Impervious, Inflow Depth = 0.10" for 10-Year event
Inflow = 0.21 cfs @ 12.13 hrs, Volume= 0.016 af
Primary = 0.21 cfs @ 12.13 hrs, Volume= 0.016 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs

Summary for Link DP-2P: Design Point

Inflow Area = 0.013 ac, 0.00% Impervious, Inflow Depth = 1.33" for 10-Year event
Inflow = 0.02 cfs @ 12.13 hrs, Volume= 0.001 af
Primary = 0.02 cfs @ 12.13 hrs, Volume= 0.001 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs

Summary for Link DP-3P: Design Point

Inflow Area = 0.029 ac, 0.00% Impervious, Inflow Depth = 1.33" for 10-Year event
Inflow = 0.04 cfs @ 12.13 hrs, Volume= 0.003 af
Primary = 0.04 cfs @ 12.13 hrs, Volume= 0.003 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs

Hydrology

NRCC 24-hr D 10-Year Rainfall=4.93"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 13

Summary for Link DP-4P: Design Point

Inflow Area = 0.007 ac, 0.00% Impervious, Inflow Depth = 1.33" for 10-Year event
Inflow = 0.01 cfs @ 12.13 hrs, Volume= 0.001 af
Primary = 0.01 cfs @ 12.13 hrs, Volume= 0.001 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs

Hydrology

NRCC 24-hr D 25-Year Rainfall=6.06"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 14

Time span=0.00-48.00 hrs, dt=0.01 hrs, 4801 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment PR-1A:	Runoff Area=33,035 sf 78.10% Impervious Runoff Depth=4.90" Tc=5.0 min CN=90 Runoff=4.02 cfs 0.310 af
Subcatchment PR-1B:	Runoff Area=45,630 sf 64.22% Impervious Runoff Depth=4.36" Tc=5.0 min CN=85 Runoff=5.11 cfs 0.381 af
Subcatchment PR-1C: Subcatchment-PR-1C	Runoff Area=6,115 sf 0.00% Impervious Runoff Depth=2.05" Tc=5.0 min CN=61 Runoff=0.33 cfs 0.024 af
Subcatchment PR-2: Subcatchment-PR-2	Runoff Area=548 sf 0.00% Impervious Runoff Depth=2.05" Tc=5.0 min CN=61 Runoff=0.03 cfs 0.002 af
Subcatchment PR-3: Subcatchment-PR-3	Runoff Area=1,281 sf 0.00% Impervious Runoff Depth=2.05" Tc=5.0 min CN=61 Runoff=0.07 cfs 0.005 af
Subcatchment PR-4: Subcatchment-PR-4	Runoff Area=319 sf 0.00% Impervious Runoff Depth=2.05" Tc=5.0 min CN=61 Runoff=0.02 cfs 0.001 af
Pond 1P: Infiltration Pond #1	Peak Elev=85.47' Storage=8,107 cf Inflow=4.02 cfs 0.310 af Discarded=0.12 cfs 0.300 af Primary=0.00 cfs 0.000 af Outflow=0.12 cfs 0.300 af
Pond 2P: Infiltration Pond #2	Peak Elev=79.93' Storage=10,596 cf Inflow=5.11 cfs 0.381 af Discarded=0.12 cfs 0.330 af Primary=0.00 cfs 0.000 af Outflow=0.12 cfs 0.330 af
Link DP-1P: Design Point	Inflow=0.33 cfs 0.024 af Primary=0.33 cfs 0.024 af
Link DP-2P: Design Point	Inflow=0.03 cfs 0.002 af Primary=0.03 cfs 0.002 af
Link DP-3P: Design Point	Inflow=0.07 cfs 0.005 af Primary=0.07 cfs 0.005 af
Link DP-4P: Design Point	Inflow=0.02 cfs 0.001 af Primary=0.02 cfs 0.001 af

Total Runoff Area = 1.996 ac Runoff Volume = 0.723 af Average Runoff Depth = 4.35"
36.61% Pervious = 0.731 ac 63.39% Impervious = 1.265 ac

Hydrology

NRCC 24-hr D 25-Year Rainfall=6.06"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 15

Summary for Subcatchment PR-1A: Subcatchment-PR-1A

Runoff = 4.02 cfs @ 12.12 hrs, Volume= 0.310 af, Depth= 4.90"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 25-Year Rainfall=6.06"

Area (sf)	CN	Description
25,800	98	Roofs, HSG A
7,235	61	>75% Grass cover, Good, HSG B
33,035	90	Weighted Average
7,235		21.90% Pervious Area
25,800		78.10% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Summary for Subcatchment PR-1B: Subcatchment-PR-1B

Runoff = 5.11 cfs @ 12.12 hrs, Volume= 0.381 af, Depth= 4.36"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 25-Year Rainfall=6.06"

Area (sf)	CN	Description
29,304	98	Paved parking, HSG A
16,326	61	>75% Grass cover, Good, HSG B
45,630	85	Weighted Average
16,326		35.78% Pervious Area
29,304		64.22% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Summary for Subcatchment PR-1C: Subcatchment-PR-1C

Runoff = 0.33 cfs @ 12.13 hrs, Volume= 0.024 af, Depth= 2.05"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 25-Year Rainfall=6.06"

Area (sf)	CN	Description
6,115	61	>75% Grass cover, Good, HSG B
6,115		100.00% Pervious Area

Hydrology

NRCC 24-hr D 25-Year Rainfall=6.06"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 16

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Summary for Subcatchment PR-2: Subcatchment-PR-2

Runoff = 0.03 cfs @ 12.13 hrs, Volume= 0.002 af, Depth= 2.05"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 25-Year Rainfall=6.06"

Area (sf)	CN	Description
548	61	>75% Grass cover, Good, HSG B
548		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Summary for Subcatchment PR-3: Subcatchment-PR-3

Runoff = 0.07 cfs @ 12.13 hrs, Volume= 0.005 af, Depth= 2.05"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 25-Year Rainfall=6.06"

Area (sf)	CN	Description
1,281	61	>75% Grass cover, Good, HSG B
1,281		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Summary for Subcatchment PR-4: Subcatchment-PR-4

Runoff = 0.02 cfs @ 12.13 hrs, Volume= 0.001 af, Depth= 2.05"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 25-Year Rainfall=6.06"

Area (sf)	CN	Description
319	61	>75% Grass cover, Good, HSG B
319		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Hydrology

NRCC 24-hr D 25-Year Rainfall=6.06"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 17

Summary for Pond 1P: Infiltration Pond #1

Inflow Area = 0.758 ac, 78.10% Impervious, Inflow Depth = 4.90" for 25-Year event
Inflow = 4.02 cfs @ 12.12 hrs, Volume= 0.310 af
Outflow = 0.12 cfs @ 16.65 hrs, Volume= 0.300 af, Atten= 97%, Lag= 272.0 min
Discarded = 0.12 cfs @ 16.65 hrs, Volume= 0.300 af
Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Stor-Ind method, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
Peak Elev= 85.47' @ 16.65 hrs Surf.Area= 5,032 sf Storage= 8,107 cf

Plug-Flow detention time= 760.2 min calculated for 0.300 af (97% of inflow)
Center-of-Mass det. time= 740.1 min (1,534.4 - 794.3)

Volume	Invert	Avail.Storage	Storage Description
#1	83.00'	10,975 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
83.00	1,580	0	0
84.00	2,940	2,260	2,260
85.00	4,340	3,640	5,900
86.00	5,810	5,075	10,975

Device	Routing	Invert	Outlet Devices
#1	Discarded	83.00'	1.020 in/hr Exfiltration over Surface area
#2	Primary	85.50'	30.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s) 0.5' Crest Height

Discarded OutFlow Max=0.12 cfs @ 16.65 hrs HW=85.47' (Free Discharge)
↑1=Exfiltration (Exfiltration Controls 0.12 cfs)

Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=83.00' (Free Discharge)
↑2=Sharp-Crested Rectangular Weir (Controls 0.00 cfs)

Summary for Pond 2P: Infiltration Pond #2

Inflow Area = 1.048 ac, 64.22% Impervious, Inflow Depth = 4.36" for 25-Year event
Inflow = 5.11 cfs @ 12.12 hrs, Volume= 0.381 af
Outflow = 0.12 cfs @ 18.57 hrs, Volume= 0.330 af, Atten= 98%, Lag= 387.1 min
Discarded = 0.12 cfs @ 18.57 hrs, Volume= 0.330 af
Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Stor-Ind method, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
Peak Elev= 79.93' @ 18.57 hrs Surf.Area= 5,016 sf Storage= 10,596 cf

Plug-Flow detention time= 863.4 min calculated for 0.330 af (87% of inflow)
Center-of-Mass det. time= 795.6 min (1,610.4 - 814.7)

Hydrology

NRCC 24-hr D 25-Year Rainfall=6.06"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 18

Volume	Invert	Avail.Storage	Storage Description
#1	77.00'	16,546 cf	Custom Stage Data (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
77.00	2,286	0	0
78.00	3,162	2,724	2,724
79.00	4,094	3,628	6,352
80.00	5,083	4,589	10,941
81.00	6,128	5,606	16,546

Device	Routing	Invert	Outlet Devices
#1	Discarded	77.00'	1.020 in/hr Exfiltration over Surface area
#2	Primary	80.10'	10.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s) 0.5' Crest Height

Discarded OutFlow Max=0.12 cfs @ 18.57 hrs HW=79.93' (Free Discharge)

↑**1=Exfiltration** (Exfiltration Controls 0.12 cfs)

Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=77.00' (Free Discharge)

↑**2=Sharp-Crested Rectangular Weir** (Controls 0.00 cfs)

Summary for Link DP-1P: Design Point

Inflow Area = 1.946 ac, 65.00% Impervious, Inflow Depth = 0.15" for 25-Year event
Inflow = 0.33 cfs @ 12.13 hrs, Volume= 0.024 af
Primary = 0.33 cfs @ 12.13 hrs, Volume= 0.024 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs

Summary for Link DP-2P: Design Point

Inflow Area = 0.013 ac, 0.00% Impervious, Inflow Depth = 2.05" for 25-Year event
Inflow = 0.03 cfs @ 12.13 hrs, Volume= 0.002 af
Primary = 0.03 cfs @ 12.13 hrs, Volume= 0.002 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs

Summary for Link DP-3P: Design Point

Inflow Area = 0.029 ac, 0.00% Impervious, Inflow Depth = 2.05" for 25-Year event
Inflow = 0.07 cfs @ 12.13 hrs, Volume= 0.005 af
Primary = 0.07 cfs @ 12.13 hrs, Volume= 0.005 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs

Hydrology

NRCC 24-hr D 25-Year Rainfall=6.06"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 19

Summary for Link DP-4P: Design Point

Inflow Area = 0.007 ac, 0.00% Impervious, Inflow Depth = 2.05" for 25-Year event
Inflow = 0.02 cfs @ 12.13 hrs, Volume= 0.001 af
Primary = 0.02 cfs @ 12.13 hrs, Volume= 0.001 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs

Hydrology

NRCC 24-hr D 100-Year Rainfall=7.80"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 20

Time span=0.00-48.00 hrs, dt=0.01 hrs, 4801 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment PR-1A:	Runoff Area=33,035 sf 78.10% Impervious Runoff Depth=6.61" Tc=5.0 min CN=90 Runoff=5.31 cfs 0.418 af
Subcatchment PR-1B:	Runoff Area=45,630 sf 64.22% Impervious Runoff Depth=6.02" Tc=5.0 min CN=85 Runoff=6.93 cfs 0.526 af
Subcatchment PR-1C: Subcatchment-PR-1C	Runoff Area=6,115 sf 0.00% Impervious Runoff Depth=3.29" Tc=5.0 min CN=61 Runoff=0.54 cfs 0.039 af
Subcatchment PR-2: Subcatchment-PR-2	Runoff Area=548 sf 0.00% Impervious Runoff Depth=3.29" Tc=5.0 min CN=61 Runoff=0.05 cfs 0.003 af
Subcatchment PR-3: Subcatchment-PR-3	Runoff Area=1,281 sf 0.00% Impervious Runoff Depth=3.29" Tc=5.0 min CN=61 Runoff=0.11 cfs 0.008 af
Subcatchment PR-4: Subcatchment-PR-4	Runoff Area=319 sf 0.00% Impervious Runoff Depth=3.29" Tc=5.0 min CN=61 Runoff=0.03 cfs 0.002 af
Pond 1P: Infiltration Pond #1	Peak Elev=85.55' Storage=8,490 cf Inflow=5.31 cfs 0.418 af Discarded=0.12 cfs 0.319 af Primary=1.01 cfs 0.082 af Outflow=1.13 cfs 0.401 af
Pond 2P: Infiltration Pond #2	Peak Elev=80.17' Storage=11,826 cf Inflow=6.93 cfs 0.526 af Discarded=0.12 cfs 0.354 af Primary=0.65 cfs 0.104 af Outflow=0.77 cfs 0.459 af
Link DP-1P: Design Point	Inflow=1.22 cfs 0.225 af Primary=1.22 cfs 0.225 af
Link DP-2P: Design Point	Inflow=0.05 cfs 0.003 af Primary=0.05 cfs 0.003 af
Link DP-3P: Design Point	Inflow=0.11 cfs 0.008 af Primary=0.11 cfs 0.008 af
Link DP-4P: Design Point	Inflow=0.03 cfs 0.002 af Primary=0.03 cfs 0.002 af

Total Runoff Area = 1.996 ac Runoff Volume = 0.995 af Average Runoff Depth = 5.98"
36.61% Pervious = 0.731 ac 63.39% Impervious = 1.265 ac

Hydrology

NRCC 24-hr D 100-Year Rainfall=7.80"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 21

Summary for Subcatchment PR-1A: Subcatchment-PR-1A

Runoff = 5.31 cfs @ 12.12 hrs, Volume= 0.418 af, Depth= 6.61"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 100-Year Rainfall=7.80"

Area (sf)	CN	Description
25,800	98	Roofs, HSG A
7,235	61	>75% Grass cover, Good, HSG B
33,035	90	Weighted Average
7,235		21.90% Pervious Area
25,800		78.10% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Summary for Subcatchment PR-1B: Subcatchment-PR-1B

Runoff = 6.93 cfs @ 12.12 hrs, Volume= 0.526 af, Depth= 6.02"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 100-Year Rainfall=7.80"

Area (sf)	CN	Description
29,304	98	Paved parking, HSG A
16,326	61	>75% Grass cover, Good, HSG B
45,630	85	Weighted Average
16,326		35.78% Pervious Area
29,304		64.22% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Summary for Subcatchment PR-1C: Subcatchment-PR-1C

Runoff = 0.54 cfs @ 12.13 hrs, Volume= 0.039 af, Depth= 3.29"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 100-Year Rainfall=7.80"

Area (sf)	CN	Description
6,115	61	>75% Grass cover, Good, HSG B
6,115		100.00% Pervious Area

Hydrology

NRCC 24-hr D 100-Year Rainfall=7.80"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 22

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Summary for Subcatchment PR-2: Subcatchment-PR-2

Runoff = 0.05 cfs @ 12.13 hrs, Volume= 0.003 af, Depth= 3.29"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 100-Year Rainfall=7.80"

Area (sf)	CN	Description
548	61	>75% Grass cover, Good, HSG B
548		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Summary for Subcatchment PR-3: Subcatchment-PR-3

Runoff = 0.11 cfs @ 12.13 hrs, Volume= 0.008 af, Depth= 3.29"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 100-Year Rainfall=7.80"

Area (sf)	CN	Description
1,281	61	>75% Grass cover, Good, HSG B
1,281		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Summary for Subcatchment PR-4: Subcatchment-PR-4

Runoff = 0.03 cfs @ 12.13 hrs, Volume= 0.002 af, Depth= 3.29"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
NRCC 24-hr D 100-Year Rainfall=7.80"

Area (sf)	CN	Description
319	61	>75% Grass cover, Good, HSG B
319		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry, Tc (min)

Hydrology

NRCC 24-hr D 100-Year Rainfall=7.80"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 23

Summary for Pond 1P: Infiltration Pond #1

Inflow Area = 0.758 ac, 78.10% Impervious, Inflow Depth = 6.61" for 100-Year event
Inflow = 5.31 cfs @ 12.12 hrs, Volume= 0.418 af
Outflow = 1.13 cfs @ 12.37 hrs, Volume= 0.401 af, Atten= 79%, Lag= 15.1 min
Discarded = 0.12 cfs @ 12.37 hrs, Volume= 0.319 af
Primary = 1.01 cfs @ 12.37 hrs, Volume= 0.082 af

Routing by Stor-Ind method, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
Peak Elev= 85.55' @ 12.37 hrs Surf.Area= 5,143 sf Storage= 8,490 cf

Plug-Flow detention time= 614.9 min calculated for 0.401 af (96% of inflow)
Center-of-Mass det. time= 590.7 min (1,375.2 - 784.5)

Volume	Invert	Avail.Storage	Storage Description
#1	83.00'	10,975 cf	Custom Stage Data (Prismatic) Listed below (Recalc)
Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
83.00	1,580	0	0
84.00	2,940	2,260	2,260
85.00	4,340	3,640	5,900
86.00	5,810	5,075	10,975

Device	Routing	Invert	Outlet Devices
#1	Discarded	83.00'	1.020 in/hr Exfiltration over Surface area
#2	Primary	85.50'	30.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s) 0.5' Crest Height

Discarded OutFlow Max=0.12 cfs @ 12.37 hrs HW=85.55' (Free Discharge)
↑**1=Exfiltration** (Exfiltration Controls 0.12 cfs)

Primary OutFlow Max=0.99 cfs @ 12.37 hrs HW=85.55' (Free Discharge)
↑**2=Sharp-Crested Rectangular Weir** (Weir Controls 0.99 cfs @ 0.71 fps)

Summary for Pond 2P: Infiltration Pond #2

Inflow Area = 1.048 ac, 64.22% Impervious, Inflow Depth = 6.02" for 100-Year event
Inflow = 6.93 cfs @ 12.12 hrs, Volume= 0.526 af
Outflow = 0.77 cfs @ 12.85 hrs, Volume= 0.459 af, Atten= 89%, Lag= 43.9 min
Discarded = 0.12 cfs @ 12.85 hrs, Volume= 0.354 af
Primary = 0.65 cfs @ 12.85 hrs, Volume= 0.104 af

Routing by Stor-Ind method, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs
Peak Elev= 80.17' @ 12.85 hrs Surf.Area= 5,262 sf Storage= 11,826 cf

Plug-Flow detention time= 690.2 min calculated for 0.459 af (87% of inflow)
Center-of-Mass det. time= 624.2 min (1,427.4 - 803.2)

Hydrology

NRCC 24-hr D 100-Year Rainfall=7.80"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 24

Volume	Invert	Avail.Storage	Storage Description
#1	77.00'	16,546 cf	Custom Stage Data (Prismatic) Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
77.00	2,286	0	0
78.00	3,162	2,724	2,724
79.00	4,094	3,628	6,352
80.00	5,083	4,589	10,941
81.00	6,128	5,606	16,546

Device	Routing	Invert	Outlet Devices
#1	Discarded	77.00'	1.020 in/hr Exfiltration over Surface area
#2	Primary	80.10'	10.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s) 0.5' Crest Height

Discarded OutFlow Max=0.12 cfs @ 12.85 hrs HW=80.17' (Free Discharge)

↑**1=Exfiltration** (Exfiltration Controls 0.12 cfs)

Primary OutFlow Max=0.63 cfs @ 12.85 hrs HW=80.17' (Free Discharge)

↑**2=Sharp-Crested Rectangular Weir** (Weir Controls 0.63 cfs @ 0.89 fps)

Summary for Link DP-1P: Design Point

Inflow Area = 1.946 ac, 65.00% Impervious, Inflow Depth = 1.39" for 100-Year event
Inflow = 1.22 cfs @ 12.77 hrs, Volume= 0.225 af
Primary = 1.22 cfs @ 12.77 hrs, Volume= 0.225 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs

Summary for Link DP-2P: Design Point

Inflow Area = 0.013 ac, 0.00% Impervious, Inflow Depth = 3.29" for 100-Year event
Inflow = 0.05 cfs @ 12.13 hrs, Volume= 0.003 af
Primary = 0.05 cfs @ 12.13 hrs, Volume= 0.003 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs

Summary for Link DP-3P: Design Point

Inflow Area = 0.029 ac, 0.00% Impervious, Inflow Depth = 3.29" for 100-Year event
Inflow = 0.11 cfs @ 12.13 hrs, Volume= 0.008 af
Primary = 0.11 cfs @ 12.13 hrs, Volume= 0.008 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs

Hydrology

NRCC 24-hr D 100-Year Rainfall=7.80"

Prepared by Dana F. Perkins, Inc.

HydroCAD® 10.00-22 s/n 00444 © 2018 HydroCAD Software Solutions LLC

Page 25

Summary for Link DP-4P: Design Point

Inflow Area = 0.007 ac, 0.00% Impervious, Inflow Depth = 3.29" for 100-Year event
Inflow = 0.03 cfs @ 12.13 hrs, Volume= 0.002 af
Primary = 0.03 cfs @ 12.13 hrs, Volume= 0.002 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-48.00 hrs, dt= 0.01 hrs

Stormwater Management Permit

Proposed Self Storage Facility

**43 River Road
Andover, Massachusetts**

Hydraulic Calculations

Prepared for:

**3P Properties, LLC
665 Church Street
Whitinsville, MA 01588**

Prepared by:

**Dana F. Perkins, Inc.
1057 East Street
Tewksbury, MA 01876**

Submitted To:

Town of Andover ~ Planning Board

Dana F. Perkins, Inc.
 Consulting Engineers & Land Surveyors
 1057 East Street
 Tewksbury, MA 01876



LOCATION: Proposed Self Storage Facility
43 River Road, Andover; MA

COMPUTED BY: AMP
CHECKED BY: EED

DATE: July 11, 2022
SHEET: 1 of 1

25-YEAR STORM
DESIGN EVENT

LOCATION		AREA x COEFFICIENT						TIME OF FLOW		DESIGN						PROFILE							
FROM	TO	PERVIOUS			IMPERVIOUS			TOTAL	Total	I	Q	ALL PIPES ARE CIRCULAR HDPE UNLESS NOTED						LENGTH	FALL	RIM ELEV.		INVERT ELEV.	
		AREA	C	SUBTOTAL	AREA	C	SUBTOTAL					PIPE SIZE	SLOPE	n	CAPACITY FULL	VELOCITY FULL	UPPER			LOWER			
		[acres]			[acres]			[min.]	[in/hr]	[c. f. s.]	[inches]	[ft. per ft.]		[c. f. s.]	[ft. / sec]	[ft.]	[ft.]	[ft.]	[ft.]	[ft.]			
CB #1	DMH #1	0.000	0.30	0.000	0.088	0.90	0.079	0.079	5.00	6.2	0.49	12	0.005	0.012	2.73	3.48	196	0.98	85.80	82.30	81.32		
CB #2	DMH #1	0.000	0.30	0.000	0.096	0.90	0.086	0.086	5.00	6.2	0.53	12	0.005	0.012	2.73	3.48	20	0.10	85.80	82.30	82.20		
CB #4	DMH #2	0.000	0.30	0.000	0.107	0.90	0.097	0.097	5.00	6.2	0.60	12	0.005	0.012	2.73	3.48	78	0.39	85.80	82.30	81.91		
CB #5	DMH #2	0.000	0.30	0.000	0.088	0.90	0.079	0.079	5.00	6.2	0.49	12	0.005	0.012	2.73	3.48	20	0.10	85.80	82.30	82.20		
CB #6	DMH #3	0.000	0.30	0.000	0.092	0.90	0.082	0.082	5.00	6.2	0.51	12	0.005	0.012	2.73	3.48	90	0.45	265.60	262.60	262.15		
DMH #2	DMH #3	-	-	-	-	-	-	0.175	5.00	6.2	1.08	12	0.005	0.012	2.73	3.48	44	0.22	85.80	82.30	82.08		
CB #3	DMH #4	0.000	0.30	0.000	0.174	0.90	0.156	0.156	5.00	6.2	0.96	12	0.005	0.012	2.73	3.48	36	0.18	85.60	82.10	81.92		
DMH #1	DMH #4	-	-	-	-	-	-	0.165	5.00	6.2	1.02	12	0.005	0.012	2.73	3.48	116	0.58	86.40	81.22	80.64		
DMH #3	DMH #4	-	-	-	-	-	-	0.258	5.00	6.2	1.59	12	0.005	0.012	2.73	3.48	36	0.18	86.85	80.52	80.34		
DMH #4	STC #1	-	-	-	-	-	-	0.579	5.00	6.2	3.57	12	0.040	0.012	7.73	9.85	8	0.32	86.40	79.32	79.00		
STC #1	FES #1	-	-	-	-	-	-	0.579	5.00	6.2	3.57	12	0.040	0.012	7.73	9.85	23	0.92	86.00	79.00	78.08		
TRENCH	FES #2	0.000	0.30	0.000	0.065	0.90	0.058	0.058	5.00	6.2	0.36	12	0.005	0.012	2.73	3.48	24	0.12	80.25	79.00	78.88		
ROOF	FES #3	0.000	0.30	0.000	0.592	0.90	0.533	0.533	5.00	6.2	3.28	12	0.010	0.012	3.87	4.93	38	0.38	86.80	83.38	83.00		